

DESIGN REVIEW COMMISSION AGENDA

Tuesday, July 16, 2024 – 6:30 P.M. Bartlett City Hall Assembly Chamber

Opening Prayer

Official Business of the Day

Minutes of the Tuesday, March 19, 2024 Meeting

NEW BUSINESS Site Plan

- 1. 7 Brew, 5905 Stage Road (Sam Watkins, The Reaves Firm, Inc.)
- 2. Little Caesars Retail Shell, 7418 Highway 70 (Guy Payne, Guy Payne and Associates Architects)

Open Discussion

The public shall be provided an opportunity to address the Board or Commission during an Open Discussion period at the end of each regular and special meeting of the governing body. Prior to the start of the meeting, individuals will be required to complete and present to the Clerk the Open Discussion Citizen form provided at each meeting. The Open Discussion period for regular and special meetings of the Board or Commission shall be limited to twenty (20) minutes. Individuals shall be allowed to speak for up to three (3) minutes each. Open Discussion periods will not be held for any meeting where there are no actionable items on the agenda or meetings where the governing body is conducting a disciplinary hearing for a member of the governing body or a person whose profession or activities fall within the jurisdiction of the governing body.

Adjourn

DESIGN REVIEW COMMISSION

Tuesday, July 16, 2024 – 6:30 P.M.

Bartlett City Hall Assembly Chamber

Staff Comments

NEW BUSINESS

Site Plan

1. 7 Brew, 5905 Stage Road (Sam Watkins, The Reaves Firm, Inc.)

INTRODUCTION: Mr. Sam Watkins with The Reaves Firm is requesting Design Review Commission approval of a Site Plan for the 7 Brew Coffee Shop. The subject property is located at 5905 Stage Road, and it is within the "CG-MS" General Business with a Main Street Overlay Zoning District.

BACKGROUND: On July 1, 2024, the Planning Commission approved a Site Plan application for the 7 Brew Coffee Shop. The specifics of the approved site plan are as follows:

Site Data				
Site Area:	36,764 square feet/.844 acres			
Total Required Parking Spaces:	14			
Total Proposed Parking Spaces:	11			
Handicap Accessible:	1 van accessible			
Regular Customer Parking:	10			
Proposed Building Area:	766 total square feet			
- Coffee Shop	514 square feet			
- Cooler	252 square feet			
Greenspace/Open space:	42%			
Building Height:	One story			

<u>DISCUSSION:</u> The specific request to the DRC by the applicant is for the approval of building elevations, landscaping, lighting details, mechanical, and dumpster enclosure. The specifics of the site plan are as follows:

Elevations: The front elevation of the drive-thru only restaurant faces north toward Stage Road. The main entrance to the building is on the west elevation while there are two sliding glass doors at the drive-thru on the east elevation. All four elevations of the building will consist of Nichiha Vintage Brick in Alexandria Buff. The north, east and west elevations will have Nichiha horizontal v-groove panels in white above the water table. The windows and sliding doors will be

black aluminum with clear glass. The soffit, fascia, coping cap and curved standing seam roof will be "Pacific Blue" by Drexel Metals. The south elevation has an employee door painted to match the Nichiha Vintage Brick in Alexandria Buff. Above the employee door is a metal canopy in "Pacific Blue" by Drexel Metals.

To the west of the primary structure is a 246 square foot cooler with Nichiha Vintage Brick in Alexandria Buff on all 4 sides and Nichiha horizontal v-groove panels in white on the east and west elevations. On the north elevation of the cooler is an employee door painted to match the Nichiha Vintage Brick in Alexandria Buff.

A metal canopy connects the cooler and the restaurant then continues on covering the two drive thru lanes. The proposed canopy will be "Pacific Blue" by Drexel Metals while the steel columns, beams and pipe bollards will be Sherwin Williams "Salty Dog" (SW9177). The canopy, the curved roof and the rear canopy will have blue LED rope recessed downlighting illuminating all sides.

Landscaping: The majority of the proposed landscaping will be located around the perimeter of the property. Existing landscaping on the property will be incorporated into the site plan. The proposed landscape plantings are as follows: 34 "Tall Orange" Daylily, 32 Dwarf "Burford" Holly, 8 "Nicks Compact" Juniper, 60 "Big Blue" Liriope, 125 Variegated Liriope, 1 "Sweetbay" Magnolia, 5 Maiden Grass, 3 "Bosque" Elms, 3 "Blue Muffin" Viburnum, 10 Purple Pixie Dwarf Fringe Flower, 34 Ed Goucher Abelia, 17 "Stokes Dwarf" Yaupon Holly, "Tifway" Bermuda Sod and Bermuda Seed.

Lighting: The proposed lighting will be 1McGraw-Edison Lighting TLM 4K LED double head bronze fixtures and 3 McGraw-Edison Lighting TLM 4K LED single head bronze fixtures with house side shields on a 25 foot dark bronze square poles will be lighting the parking lot. Under the metal canopy, there will be 26 Juno Type B 4K LED canopy lights. The Average foot-candles for the proposed site is 2.5 FC.

Mechanical: All mechanical units will be located on the roof screened by a parapet wall.

Dumpster Enclosure: The dumpster enclosure is located on the southwest side of the property. The dumpster enclosure will consist of a split face CMU painted Sherwin Williams "Toile Red" (SW 00006) to match the building elevations. The metal gate panels will be painted Sherwin Williams "Salty Dog" (SW9177). The enclosure will be screened with shrubs.

Recommendation: Approval with Conditions.

Planning Comments:

1. The Bartlett Zoning Ordinance requires 14 spaces per 1,000 square feet of building space for a Fast Food Restaurant land use. The 514 square foot coffee shop is drive through only and has an occupancy load of 4 persons. The applicant has provided 11 parking spaces, which includes 1 ADA compliant space. On July 1, 2024, per Ordinance 15-6, the Planning Commission, at site plan review voted to approve a minimum number of required parking spaces (11 spaces) different from those listed in Figure VI-12a of the Bartlett Zoning Ordinance Parking Design Requirements.

Planning Conditions:

- 1. According to Article VI, Part III, D.4 all parking spaces must be a maximum distant of 75 feet from a tree.
- 2. The applicant shall include the parking space details on the Building Summary Table on page SA1.
- 3. The applicant shall include quantity of light fixtures in lighting fixture schedule.
- 4. Irrigation and maintenance is required for all planting on the landscape plan indefinitely.
- 5. All proposed signage shall be submitted on a separate application to the Design Review Commission.
- 6. The owner/applicant shall identify all utilities on site by contacting Tennessee One Call at 811 before commencing any site work.
- 7. The applicant must submit a form board survey to Code Enforcement detailing the building setbacks and landscape buffers from all property lines for building permit approval.
- 8. Owner/applicant shall be present at the meetings in order to make decisions relative to any changes that may be suggested by the Design Review Commission.

Engineering Conditions: General:

- 1) A Commercial Site Plan contract may be required and will be prepared by Engineering and submitted to the developer/engineer for review to cover the fees to be paid to the City of Bartlett.
- 2) If required, Applicant/ Engineer shall provide a <u>digital set of drawing</u> files showing the sanitary sewer lines, drainage lines, lot lines and all improvements in AutoCAD format to <u>dhubbard@cityofbartlett.org</u> and <u>ecampbell@cityofbartlett.org</u> for use in the preparation of the Water Design Plan. This plan will be coordinated with the site design engineer to resolve any conflicts.
- 3) A SWPPP and a TDEC NPDES permit may be required and shall be submitted to the TDEC and the City of Bartlett Engineering office.

- 4) Detention will be required as part of this development as the Storm Water Ordinance specifies a zero increase in post development.
- 5) All new utilities shall be underground.
- 6) Correct all markups.

Utility Plan:

- 7) Existing water meter is to be relocated out of driveway.
- 8) Sewer cleanout in driveway to be per City of Bartlett specifications.
- 9) An irrigation water service and meter is required.

Traffic Control Plan:

10) A traffic control plan is not required for work identified on this plan set.

2. Little Caesars Retail Shell, 7418 Highway 70 (Guy Payne, Guy Payne and Associates Architects)

INTRODUCTION: Mr. Guy Payne with Guy Payne and Associates Architects is requesting Design Review Commission approval of a Site Plan for a new four tenant retail building. The subject property is located on the vacant lot located at 7418 Highway 70, and it is within the "C-G" General Business Zoning District.

BACKGROUND: The subject property is the former location of the Siesta Motel building that was demolished in August 2014. The subject property is a legal lot of record that was created by deed in Book 3054, Page 1 in January 1953. This recorded deed predates the Subdivision Ordinance date of March 6, 1956, so the subject property is eligible for a building permit subject to Site Plan approvals from the Planning Commission and Design Review Commission.

On March 4, 2024, the Planning Commission approved a site plan for the subject property. The specifics of the approved site plan were as follows:

Site Data	
Site Area:	2.05 acres/89,298 square feet
Total Required Parking Spaces:	30
(One space per 200 square feet)	
Total Proposed Parking Spaces:	32
Handicap Accessible:	2 van accessible
Regular:	30
Proposed Building Area:	6,000 square feet
Greenspace/Open space:	69%
Building Height:	< 20 feet

<u>DISCUSSION</u>: The specific request to the DRC by the applicant is for the approval of building elevations, landscaping, and lighting details as follows:

Elevations: The front of the building is the south elevation. The front elevation consists of red brick and a metal mansard painted sierra tan. A metal awning painted sierra tan will be above the four aluminum storefront doors. The door and window trim will be aluminum painted sierra tan with clear glass. The side elevations are the east and west elevations, and they will consist of red brick and a metal mansard painted sierra tan. The east elevation will have no windows, and the west elevation will have a drive thru window for a proposed Little Caesars location. The rear elevation is the north elevation, and it will consist of red brick and a metal mansard painted sierra tan. Four service doors will be located on the north elevation. All doors will be sierra tan to match the metal awnings on the front elevation. All downspots and metal copings will be painted sierra tan.

Dumpster Enclosure: The dumpster enclosure is located to the rear of the building in the northeast corner of the property. The dumpster enclosure will consist of six foot tall wood pickets with wood picket composite gate panels attached to a steel frome with steel drop pins.

Mechanical: All mechanical units will be located on the rooftop and screened from public view behind a parapet wall.

Landscaping: The majority of the landscaping is proposed around the perimeter of the property with some internal landscape islands. The proposed landscape plantings are as follows: 16-Eastern Red Cedar, 4-Tulip Poplar, 3-Star Magnolia, 5-Evergreen Sweetbay, 4-Green Gable Black Gum, 4-Shoal Creek Chaste Tree, 31-Blue Cascade Distylium, 38-Carissa Holly, 27-Dwarf Yaupon Holly, 17-Miss Patricia Holly, 22-Little Kitten Maiden Grass, 45-Walker's Low Catmint, 29-Danica Arborvitae, and Tifway 419 Bermuda sod.

Lighting: The site will have eight Lithonia Lighting RSX1 4K LED pole fixtures on 20 foot tall dark bronze poles and an 18 inch tall concrete base with EGS shields, eight Lithonia Lighting WPXI full cutoff downward 4K LED wall packs, and eight Duallite full cutoff downward 4K LED wall sconce fixtures. There is no lighting spillover from the site. The overall foot candle average is 0.62 with the parking lot specific areas maintaining a 2.0 foot candle average.

Recommendation: Approval with conditions.

Planning Conditions:

1. All proposed signage shall be submitted on a separate application to the Design Review Commission.

- 2. Applicant shall identify all paint colors and numbers on exterior material legend.
- 3. Applicant shall identify all exterior materials by product name and style/color numbers on exterior material legend.
- 4. All mechanical equipment shall be screened from public view.
- 5. Applicant shall add Tree Density Unit Table to the landscape plan.
- 6. Applicant shall install shrubs along the Highway 70 frontage between the trees utilized for commercial streetscape Plate 23C modified.
- 7. The applicant shall show the required Landscape Plate 23D plantings on the landscape plan along the east property line.
- 8. The applicant shall install the required Landscape Plate 23D fence along the east property line, or they may meet with the residential neighbor to negotiate the fence to be installed along the east property line.
- 9. Irrigation and maintenance is required for all planting and residential buffer fencing on the landscape plan for the life of the project.
- 10. The applicant shall revise the Architectural Site Plan to show the exact location of the drive thru speaker and menu board. Staff recommends locating the apparatus along the north (rear) elevation midway between both the east and west residential neighbors.
- 11. The applicant shall install a sound buffer wall directly across from the drive thru speaker and menu board. Staff recommends either an actual six foot tall wall or an equivalent wall of landscape.
- 12. The applicant shall revise the dumpster enclosure to consist of brick to match the building elevation with composite gate panels painted sierra tan attached to a steel frame with steel drop pins.
- 13. The applicant shall revise the front yard setback shown on the Site Plan Notes from 60 feet to 40 feet.
- 14. The applicant must submit a form board survey to Code Enforcement detailing the building setbacks and landscape buffers from all property lines for building permit approval.
- 15. The owner/applicant shall identify all utilities on site by contacting Tennessee One Call at 811 before commencing any site work.
- 16.It is recommended that the owner/applicant attend the meeting in order to make decisions relative to any changes that may be suggested by the DRC.

Engineering Conditions:

General:


- 1) A Commercial Site Plan contract may be required and will be prepared by Engineering and submitted to the developer/engineer for review to cover the fees to be paid to the City of Bartlett.
- 2) Applicant/ Engineer shall provide a <u>digital set of drawing</u> files showing the sanitary sewer lines, drainage lines, lot lines and all improvements in AutoCAD

- format to dhubbard@cityofbartlett.org and ecampbell@cityofbartlett.org for use in the preparation of the Water Design Plan. This plan will be coordinated with the site design engineer to resolve any conflicts.
- 3) A SWPPP and a TDEC permit may be required and shall be submitted to TDEC and also to the City of Bartlett Engineering office.
- 4) All new utilities shall be underground.
- 5) Site survey or existing conditions plan shall be added to set.

Plans

- 6) A traffic impact and visibility study must be done to TDOT Chapter 2 standards.
- 7) A center turn lane as well as a right turn lane for the southwest traffic will need to be added to Summer Avenue to allow for full movement. This will require a widening of the pavement and restriping in order to accommodate these extra lanes. The extra lanes must be full depth pavement and be constructed along frontage of lot. A restriping plan will be required to show these changes in the roadway. The through lanes should be at least 11' wide, the turning lanes should be at least 10' wide, and a 2' shoulder must be added on the development side. Although sidewalk, curb, and gutter will not be required, the road widening must be built according to TDOT specifications.
- 8) This site is only allowed one driveway, which shall be located approximately in the middle of the site. Sight Distance shall be checked to meet the 565' vertical sight distance per TDOT standards.
- 9) The area for future ROW must be deeded to the state of Tennessee. A dedication plat will be required for the right of way. Alternatively a full plat may be submitted to make all changes on one document. The measurement from the centerline should be 57'
- 10) The utility poles currently located roadside must be moved back out of the future asphalt widening. These poles also contain City of Bartlett fiber, which will need to be relocated at the developer's expense.
- 11) The existing water services and fire hydrant, must be adjusted back further on the property and out of the proposed future ROW that is 57-feet from the centerline of Highway 70.
- 12)2500 GPM commercial fire flow @ 20 psi residual pressure is required for this development. The city will conduct a flow test to determine existing fire flow. If the flow mentioned above is not available then a 12" water extension may be required.
- 13) There is an existing well pump house on-site that must be closed by a licensed well driller professional.
- 14) The existing drainage structure that will be in the future ROW must be moved further back on site and should serve to prevent water from the site from entering the roadway. No site water may pond on roadway.
- 15) Since this project is located in the Fletcher Creek Sewer Basin new tap approval is dependent on developer receiving written approval from the


- City of Memphis for sewer connection. If no tap exists then the developers engineer shall work with City of Memphis on holding tank design and approval.
- 16) All work in the TDOT ROW will require permitting with TDOT, including, but not limited to, Traffic Control, Striping, Construction and other new road work.
- 17) Water Extensions for utility service may be required for this site. Crossings and work in TDOT ROW may be required and will have to be permitted accordingly.
- 18) A bond will be required from the city for the site and with the state for the work in TDOT ROW.



NEW CONC. CURB & GUTTER - REF. CIVIL DRWGS.

9 EXIST'G. WATER ME'REF. CIVIL DRWGS.

EXIST'G. WATER METER (REUSE IF POSSIBLE) -



B ENL. STRIPING PLAN

1" = 10'-0"

-18" x 12" STEEL (OR

LETTERING. SYMBOL

IS ON A BRIGHT BLUE

BACKGROUND BAKED

NOTE: VAN ACCESSIBLE

"VAN" ON SITE PLAN

SIGN AT SPACE MARKED

WHITE BORDER

ENAMEL FINISH

FINISH GRADE

SIGN IS TO BE PLACED AT THE HEAD OF HANDICAP

ACCESSIBLE STALL

CONCRETE SIDEWAWLK

5'-0" MIN.

BOARD/SPEAKER SYSTEM, MENU BD. CANOPY ;

OR CLÉARANCE BAR. EMPLOYEES TAKE &

RETURN ORDERS TO CUSTOMERS AT THIER) VEHICLE IN THE DRIVE-THRU LANES

ALUMINUM) SIGN WITH

CODE SUMMARY

BUILDING CODE: ELECT. CODE: **FUEL CODE:** FIRE CODE:

2021 INTERNATIONAL BUILDING CODE 2021 INTERNATIONAL PLUMBING CODE 2021 INTERNATIONAL MECHANICAL CODE 2017 NATIONAL ELECTRICAL CODE 2021 INTERNATIONAL FUEL GAS CODE 2021 INTERNATIONAL FIRE CODE 2017 ICC A117.1 ACCESSIBILITY CODE

20'-0"±

CG-MS

514 SQ. FT. (bldg.)

246 SQ. FT. (walk-in)

BUILDING SUMMARY

NUMBER OF STORIES: BUILDING HEIGHT: BUILDING AREA: BUILDING TYPE USE GROUP:

-√99'-10 3/4")

√ 99'−11"

OCCUPANT LOAD: SPRINKLER SYSTEM: **EMERGENCY LIGHTING:** NUMBER OF EXITS REQUIRED: NUMBER OF EXITS PROVIDED: MAXIMUM TRAVEL DISTANCE: — GALVANIZED METAL SIGN ZONING:


ACCESSIBILITY (2) SYMBOL (PAINTED)

Site Striping

Asphault paving surfaces shall have blue striping with the remaing traffic symbols / text to be white. Reference example below and parking lot paint color chart.



Concreate paving surfaces shall have blue striping with the remaing traffic symbols / text to be red. Reference example below and parking lot paint color chart.



1'-5"

2'-10"

Parking Lot Striping Colors & Paint

Asphault Paint Colors:

White - Pantone 000C Blue - Pantone 293

Concreate Paint Colors:

Red - Pantone 202 Blue - Pantone 293

PMS 000C R: 255 G: 255 B: 255 HEX: ffffff

PMS 293 B: 165

HEX: 003da5

PMS 202 G: 36 B: 50 HEX: 8a2432

Traffic Paint Type:


Sherwin- Williams Pro Park, Setfast, Hotline or an approved equal.

6-14-2024 7-3-2024

10. CONTROL JOINTS SHALL BE 1" DEEP AND 1/4" WIDE.

ADA SIDEWALK AND RAMP NOTES

- THE CROSS SLOPE OF A SIDEWALK SHALL BE 2% (1/4" / PER 12") MAX. AND 1% (1/8" / PER 12") MIN. THE SLOPE CAN BE TOWARD THE PAVEMENT OR AWAY FROM THE PAVEMENT AS LONG AS POSITIVE DRAINAGE IS MAINTAINED.
- CURB RAMPS SHALL HAVE A MIN. WIDTH OF 48 INCHES. THE CURB RAMPS
- SHALL HAVE A MAXIMUM LONGITUDINAL SLOPE OF (1" / PER 12") A LANDING THE WIDTH (W) OF THE CURB RAMP AND FIVE FEET IN LENGTH
- SHALL BE CONSTRUCTED AT THE TOP OF CURB RAMPS. THE SLOPE OF THE LANDING SHALL NOT EXCEED 2% IN ANY DIRECTION.
- 4. CARE SHALL BE TAKEN TO ENSURE A UNIFORM GRADE ON RAMPS, FREE OF SAGS AND SHORT GRADE CHANGES.
- . THE NORMAL GUTTER LINE PROFILE SHALL BE MAINTAINED THROUGH THE AREAS
- 6. SIDEWALKS THAT ARE PART OF A ADA ACCESSIBLE ROUTE AND ALL CURB AND ADA RAMPS SHALL BE CONSTRUCTED TO MEET ALL ADA REQUIREMENTS AND TOLERANCES.
- 7. SIDEWALKS ABUTTING ASPHALT SHALL HAVE A THICKENED EDGE.
- 8. PROVIDE CONTROL JOINTS AT INTERVALS EQUAL TO CONCRETE SIDEWALK WIDTH, BUT IN NO CASE GREATER THAN 10'-0".
- 9. CONTROL JOINTS MAY BE MADE WITH A GROOVING TOOL AT HE TIME OF FINISHING OR WITH A CONCRETE SAW AFTER CONCRETE HAS SUFFICIENTLY
- 11. PROVIDE EXPANSION JOINTS AT MAXIMUM OF 32'-0" INTERVALS AND AT EXISTING STRUCTURES OR CONCRETE.




7/3/2024 THE DESIGN AND DETAILS
DISCLOSED HEREIN ARE THE
EXCLUSIVE PROPERTY OF
RODGEN AND BAKER, AIA AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT HIS PRIOR WRITTEN CONSENT. RODGER W. BAKER, AIA

> **ARCHITECTURAL** SITE PLAN

DATE


DRAWN BY: RC CHECKED BY:

SHEET NO. SA1



BAKER DESIGN GROUP, PA
RODGER W BAKER ARCHITECT, AIA NCARB
135 N. Main St. Wichita KS 67202 316.267.7142
rodger@bakerdesigngrouppa.com

7 Brew 5905 Stage Rd. SARTLETT, TN. 38133



THE DESIGN AND DETAILS
DISCLOSED HEREIN ARE THE
EXCLUSIVE PROPERTY OF
RODGER W. BAKER, AIA AND
SHALL NOT BE COPIED OR
REPRODUCED IN WHOLE OR
IN PART WITHOUT HIS PRIOR
WRITTEN CONSENT.

RODGER W. BAKER, AIA


TRASH ENCLOSURE

DATE

6-14-2024

DRAWN BY:
RC
CHECKED BY:
RB
SHEET NO.

SA1.1




	LIGHTING FIXTURE SCHEDULE							
SYM	DESCRIPTION	MFGR.	CAT No.	TYPE	LAMP CODE	-MOUNTING	NOTES	
SA	DOUBLE HEAD POLE LIGHT	McGRAW EDISON	TLM-E04-LED-E1-SL4-BZ-MA1011-XX	LED	12,896 lm (97W) x2	ON 25' POLE	1	
SB	SINGLE HEAD POLE LIGHT	McGRAW EDISON	TLM-E04-LED-E1-SL4HSS-BZ-SMA1010-XX	LED	11,816 lm (97W)	ON 25' POLE	2	
В	EXTERIOR CANOPY LIGHT	JUNO	65BEMN SWW5 90CRU 4K M6	} ED	900 lm (10.4W)	RECESS / CANOPY	3	


- I. DOUBLE HEAD FIXTURE MOUNTED ON 25' POLE # SSS5A25SFM2X. SEE POLE BASE DETAIL. ~~~~~
- 2. SINGLE HEAD FIXTURE MOUNTED ON 25' POLE # SSS5A25SFM IX. SEE POLE BASE DETAIL.

NORTH


3. FIXTURE IS LISTED AS SUITABLE FOR USE IN WET LOCATION. $\frac{215}{100}$

CALCULATION SUMMARY						
LABEL	UNITS	AVG.	MAX.	MIN.		
FULL SITE @ PROPERTY LINE	FC	2.5	9.9	0.0		
DRIVE ONLY	FC	2.0	8.5	0.0		
DRIVE WITH CANOPY	FC	2.0	23.5	0.0		
CANOPY ONLY	FC	16.6	26.5	5.9		





BrewStage Rd.
TT, TN. 38



THE DESIGN AND DETAILS
DISCLOSED HEREIN ARE THE
EXCLUSIVE PROPERTY OF
RODGER W. BAKER, AIA AND
SHALL NOT BE COPIED OR
REPRODUCED IN WHOLE OR
IN PART WITHOUT HIS PRIOR
WRITTEN CONSENT. RODGER W. BAKER, AIA

DATE 6-14-2024 7-05-2024

DRAWN BY:

SHEET NO.

CHECKED BY:

SL1.0

Electrical Site Plan Photometrics



THE DESIGN AND DETAILS
DISCLOSED HEREIN ARE THE
EXCLUSIVE PROPERTY OF
RODGER W. BAKER, AIA AND
SHALL NOT BE COPIED OR
REPRODUCED IN WHOLE OR
IN PART WITHOUT HIS PRIOR
WRITTEN CONSENT.




JUNO®



Contractor Select™

65BE 65SE SWW5

5"/6" Switchable White LED Retrofit Module



5 switchable white color temperatures to choose from via switch; 2700K, 3000K, 3500K, 4000K, 5000K CCT; 90 CRI

- Dimmable flicker-free dimming from 100% to 10%
- Baffle or smooth trim options with designer color finish trim inserts (sold separately)





Catalog Number	UPC	Description	Replaces Up To	Lumens	Input Watts	ССТ	CRI	Voltage	Finish	Dimming Protocol	Pallet qty.
65SEMW SWW5 90CRI M6	194994825197	5"/6" Switchable White LED Retrofit Module	75W Incandescent	900	10.5W	2700K-5000K	90	120V	White	100% to 10%	216
65BEMW SWW5 90CRI M6	194994160564	5"/6" Switchable White LED Retrofit Module	75W Incandescent	900	10.5W	2700K-5000K	90	120V	White	100% to 10%	180
65BEMW HL SWW5 90CRI M6	194994244950	5"/6" Switchable White LED Retrofit Module	120W Incandescent	1200	14.5W	2700K-5000K	90	120V	White	100% to 10%	270

Dimensions

CONTRACTOR SELECT 65BE 65SE SWW5

Specifications

LED RETROFIT DOWNLIGHT TRIM:

Aluminum spun reflector with deep regression for reduced glare ● Inner reflector cone funnels light through the pressed-in diffused lens • All-in-one design where LED light engine mounts directly to trim for ease of installation into existing 5" or 6" recessed housings with medium base sockets • Provided with torsion springs.

LED LIGHT ENGINE:

LEDs are mounted directly to cast aluminum housing providing superior thermal management to ensure long life • Switchable white LED color temperature technology offers 2700K, 3000K, 3500K, 4000K, 5000K all in one trim ● 90 CRI minimum ● Accommodates 120 volts AC at 60Hz • Dimmable with most standard incandescent, magnetic low voltage and electronic low voltage dimmers • For a list of compatible dimmers, see JUNOESERIES-DIM.

Diffused lens at end of mixing chamber to provide even light distribution for general illumination ● 900L is equivalent to 75W BR30 lamp ● 1200L is equivalent to 120W lamp.

Trim features quick connect plug installed as standard for installation into LEDT24 housings with mating connector ● Trim ships with a medium base socket adapter whip for installation into 5" or 6" incandescent housings with medium base sockets.

DESIGNER COLOR FINISH TRIM INSERTS: (sold separately)

Color Finish Trim inserts are accessory rings that attach to the 65BE/65SE module for a permanent finish. Trim styles include baffle or smooth in the following finishes: Black

Brush Nickel Oil-Rubbed Bronze

Rated for 50,000 hours at 70% lumen maintenance.

CSA certified to US and Canadian safety standards ● ENERGY STAR® certified product Suitable for wet location ● Air-Loc certified in accordance with ASTM E283-2004 ● NOM Certified • Can be used to comply with California Title 24 Part 6 High Efficacy LED light Source Requirements • T20 Certified.

All reports are based on published industry procedures; field performance may differ from

laboratory performance.

5-year limited warranty. Complete warranty terms located at:

www.acuitybrands.com/CustomerResources/Terms_and_conditions.aspx **Note**: Actual performance may differ as a result of end-user environment and application. All values are design or typical values, measured under laboratory conditions at 25 °C. Specifications subject to change without notice.

One Lithonia Way, Conyers, GA 30012 | (800) 705-SERV (7378) | www.acuitybrands.com © 2020-2021 Acuity Brands Lighting, Inc. All rights reserved. Rev. 11/16/21

CONTRACTOR SELECT 65BE 65SE SWW5

DESCRIPTION

The Talon luminaire is the most versatile, functionally designed. universally adaptable outdoor luminaire available. Incorporating modular LED LightBAR™ technology, the Talon luminaire brings outstanding uniformity and energy-conscious illumination to walkways, parking lots, roadways, building areas and any security lighting application. UL/ cUL

listed for wet locations. FIXTURE "SA": TLM-EO4-LED-E1-SL4-BZ-MA1011-XX

McGraw-Edison Type "SA" & "SB" Date

FIXTURE "SB": TLM-E04-LED-E1-SL4HSS-BZ-SMA1010-XX SPECIFICATION FEATURES

One-piece heavy-wall, die-cast aluminum construction with integral reveal channels along top surface of housing. Optimized for reliable operation from 40°C down to -40°C, internal cast-in wall separates optical and electrical chambers allowing components to operate cooler. Stainless steel latches and hinges allow for tool-

less opening and removal of door Choice of twelve patented, highefficiency AccuLED Optics™ distributions. Optics are precisely designed to shape the light output, maximizing efficiency and and dimming options available. application spacing. AccuLED Optics technology creates

consistent distributions with the scalability to meet customized application requirements. Offered Standard in 4000K (+/- 275K) CCT and minimum 70 CRI, Optional 3000K CCT, 5000K CCT and 5700K light control, an optional houseside shield accessory can be field or factory installed. The house-side

16-1/4" [412mm]—

O COOPER

Page 1 of 2

shield is designed to seamlessly

integrate with the SL2, SL3 or SL4

LED drivers mount to die-cast aluminum back housing for optimal tenon. 3G vibration rated. heat sinking, operation efficacy, and prolonged life. Standard drivers feature electronic universal voltage (120-277V 50/60Hz), 347V 60Hz or 480V 60Hz operation. 480V is compatible for use with 480V Wye systems only. Greater than 0.9 power factor, less than 20% harmonic distortion. All fixtures are white, dark platinum and graphite shipped standard with 10kV/10kA metallic. RAL and custom color common – and differential – mode matches available. Consult the surge protection. LightBARs feature McGraw-Edison Architectural an IP66 enclosure rating and Colors brochure for the complete

IESNA TM-21. Occupancy sensor Five-year warranty.

selection.Options to meet Buy

American Act requirements.

Extruded 8" aluminum arm includes internal bolt guides allowing for easy positioning of fixture during installation to pole or wall surface. Standard single carton packaging of housing, CCT. For the ultimate level of spill square pole arm and round pole adapter for contractor-friendly arrival of product on site. Optional mounting methods include a wall mount plate, an external mast arm that accepts 2-3/8" O.D. horizontal tenons and direct mounting to pole or wall surfaces. Tenon adapters

maintain greater than 95% lumen


maintenance at 60,000 hours per



TLM TALON MEDIUM

1 - 6 LightBARs Solid State LED ARCHITECTURAL AREA





*www.designlights.org

MA1253=10kV Circuit Module Replacement
LB/HSS-21=Field Installed House Side Shield for "E" LightBARS 20

TLM TALON MEDIUM LED Sample Number: TLM-E03-LED-E1-T3-BK

1 Todate Talling	realiser of Eight Drates Earlip Typ Voltage		Toltage	Distribution		
TLM≡Taton Medium BAA TLM= Taton Medium, Buy American Act Compliant ²⁶	E01=(1) 21 LED LightBAR E02=(2) 21 LED LightBARs E03=(3) 21 LED LightBARs E04=(4) 21 LED LightBARs E05=(5) 21 LED LightBARs E05=(6) 21 LED LightBARs F01=(1) 7 LED LightBARs F03=(3) 7 LED LightBARs F04=(4) 7 LED LightBARs F04=(4) 7 LED LightBARs F04=(6) 7 LED LightBARs F04=(6) 7 LED LightBARs	LED= Solid State Light Emitting Diodes	E1=Electronic (120-277V) 347=347V 480=480V ⁶	T2=Type II T3=Type III T4=Type IV SL2=Type II w/Spill Control SL3=Type II w/Spill Control SL3=Type IV w/Spill Control SMQ=Type V Square Medium SWQ=Type V Square Wide SXQ=Type V Square Extra Wide RW=Rectangular Wide SLL=90° Spill Light Eliminator Left SLR=90° Spill Light Eliminator Right	AP=Grey BE=Bronze BK=Black DP=Dark Platinum GM=Graphite Metallic WH=White	
Options (Add as Suffi	x)			Accessories (Order Separately) 18,27		
R=NEMA Twistlock PI PERT=NEMA 7-PIN Tv PT=Electrical Power T 2L=Two Circuits 9 7030=70 CRI / 3000K (7 7050=70 CRI / 5000K (7 7060=70 CRI / 5000K (7 7060=70 CRI / 5000K (7 8030=80 CRI / 3000K (8 8030=80 CRI / 3000K (8 8040-80 CRI	CCT 10 CCT 10 CCT 10 CCT 10 CCT 10 Plate Matches Housing Finish Arm Round or Square Pole nt ather Battery Pack (Specify 12 sor for On/Off Operation 12 ensor for Bi-Level Operation 13 Sensor for Dimming Operati	ole ⁶	MA1010-XXE-Single Tenon Adapter MA1011-XXE-3@120° Tenon Adapter MA1013-XXE-4@90° Tenon Adapter MA1013-XXE-4@90° Tenon Adapter MA1014-XXE-2@90° Tenon Adapter MA1016-XXE-3@90° Tenon Adapter MA1016-XXE-3@90° Tenon Adapter MA1018-XXE-3@120° Tenon Adapter MA1018-XXE-3@120° Tenon Adapter MA1018-XXE-3@90° Tenon Adapter MA1048-XXE-3@90° Tenon Adapter MA1048-XXE-3@90° Tenon Adapter FSIR-100=Wireless Configuration To OA/RA1016=NEMA Twistlock Photo OA/RA1021=NEMA Twistlock Photo OA/RA103=Photocontrol Shorting	for 3-1/2" O. D. Tenon for 3-1/2" O. D. Tenon for 3-1/2" O. D. Tenon or 3-1/2" O. D. Tenon for 2-3/8" O. D. Tenon for 10 Tenon for 2-3/8" O. D. Tenon for 10 Tenon for 2-3/8" O. Tenon		

LB/HSS-07=Field Installed House Side Shield for "F" LightBARS 20 WOLC-7P-10A=WaveLinx Outdoor Control Module (7-pin) 21

NOTES: 1. Customer is responsible for engineering analysis to confirm pole and fixture compatibility for all applications. Refer to our white paper WP513001EN for additional support information. 2. DesignLights Consortium™ Qualified. Refer to www.designlights.org Qualified Products List under Family Models for details. 3. 8" arm and round pole adapter included with fixture. 4. Standard 4000K CCT and minimum 70 CRI. 5. 21 LED LightBAR powered at 350mA, 7 LED LightBAR powered at 1A. 6. Only for use with 480V Wye systems. Per NEC, not for use with ungrounded systems, impedance grounded systems or corner grounded systems (commonly known as Three Phase Three Phase Three Phase High Leg

6. Only for use with 480V Wye systems. Per NEC, not for use with ungrounded systems, impedance grounded systems or corner grounded systems (commonly known as Three Phase Three Wire Delta, Three Phase High Leg Delta and Three Phase Corner Grounded Delta systems).
 7. Custom and RAL color matching available upon request. Consult your lighting representative at Cooper Lighting Solutions for more information.
 8. Must order dimming driver.
 9. Low-Level output varies by bar count specified. Consult Factory.
 10. Extended lead times apply. See website for IES files.
 11. Available with E01-E04 or F01-F04 configurations only. Rated for 25°C ambient.
 12. Sensor housed in external box mounted to the luminaire. Available in E02-E6 and F02-F6 configurations. Replace XX with mounting height in feet for proper lens selection, (e.g., MS-L25). Consult factory for additional information.
 13. Sensor housed in external box mounted to the luminaire. Available in E02-E6 and F02-F6 configurations. Replace X with number of bars operating in low output mode and replace XX with mounting height for proper lens selection, (e.g., MS/3-L25). Maximum 4 bars in low output mode. Consult factory for additional information.
 14. Only available in E02-E06 and F02-F06 includes Dimming Drivers. Not available in 347V or 480V.
 15. Replace XX with mounting height in feet for proper lens selection, (e.g., MS/DIM-L25).
 16. Available in E02-E06 and F02-F06 conly.
 17. Only for use with E12, S13 and S14 distributions. Not available with L90 or R90 options.

7. Only for use with SL2, SL3 and SL4 distributions. Not available with L90 or R90 options.

SWPD4XX=WaveLinx Sensor Only, 7'-15' 24, 25

17. Only for use with SLZ, SL3 and SL4 distributions. Not available with L90 or H90 options.

18. Replace XX with color suffix.

19. Only compatible with MS/DIM-LXX motion sensor.

20. One required for each LightBAR. Not available with L90 or R90 options.

21. PER7 is required for use with WOLC-7P-10A. The WOLC-7 cannot be used in conjunction with additional sensors or controls.

22. Cannot be used in conjunction with photocontrol or other controls systems (P, R, MS, LWR).

23. WAC Gateway required to enable field-configurability: Order WAC-PoE and WPOE-120 (10V to PoE injector) power supply if needed.


Consume the product configurations with this designated prefix are built to be compliant with the Buy American Act of 1933 (BAA). Please refer to DOMESTIC PREFERENCES website for more information. Components shipped separately may be separately analyzed under domestic preference requirements.
 Accessories sold separately will be separately analyzed under domestic preference requirements. Consult factory for further information.







March 29, 2022 9:01 AM



ASTM Grade steel base plate with ASTM A366 base cover

• Hand hole assembly 3" x 5" on 5" and 6" pole; and 2" x 4" on 4" pole • 10'-39' mounting heights • Drilled or tenon (specify)

FIXTURE "SA": SSS5A25SFM2X

April 14, 2021 5:42 PM

FIXTURE "SB": SSS5A25SFM IX DESIGN CONSIDERATIONS - VIBRATIONS AND NON-GROUND MOUNTED INSTALLATIONS

The information contained herein is for general guidance only and is not a replacement for professional judgment. Design considerations for wind-induced vibrations and non-ground mounted installations (e.g., installations on bridges or buildings) are not included in this document. Consult with a professional, and local and federal standards, before ordering to ensure product is appropriate for the intended purpose and installation location. Refer to the Cooper Lighting Solutions Light Pole White Paper for risk factors and design considerations. Learn more. NOTE: The Limited Warranty for this product specifically excludes fatigue failure or similar damage resulting from vibration, harmonic oscillation or resonance.


Specifications and dimensions subject to change without notice. Consult your lighting representative at Cooper Lighting Solutinos or visit www.cooperlighting.com for available options, accessories and


ORDERING INFORMATION

O COOPER


SSS SQUARE

STRAIGHT STEEL





ta



THE DESIGN AND DETAILS DISCLOSED HEREIN ARE THE EXCLUSIVE PROPERTY OF RODGER W. BAKER, AIA AND SHALL NOT BE COPIED OR REPRODUCED IN WHOLE OR IN PART WITHOUT HIS PRIOR WRITTEN CONSENT.

RODGER W. BAKER, AIA

DATE 6-14-2024 7-05-2024

DRAWN BY:

SHEET NO.

CHECKED BY:

Electrical Site Plan Photometrics

WOOD STEPS (UP TO ROOF)WITH WOOD HANDRAIL, TYP. BOTH SIDES OF STEPS NO FIXTURES OR EQUIP. ARE LOCATED ON THIS LEVEL. THIS AREA IS FOR ROOF ACCESS ONLY ← LIGHTED WALL SIGN - REF. EXT. ELEV'S. - STL. PIPE HANDRAIL AT ACCESS DOOR -REF. STRUCT. DRWGS. ATTIC ACCESS DOOR w/ ALUM. LADDER — LIGHTED WALL SIGN -MEZZANINE LEVEL PLAN ref. exterior elev's. —


___ LIGHTED WALL SIGN -REF. EXTERIOR ELEV'S.

FLOOR / WALL FINISHES PLAN

3/8"= 1'-0"



- 1. PROTECT-ALL VINYL FLOORING AND COVE BASE THROUGHOUT SERVICE AREA AND TOILET, TYP.
- 2. REF. FINISHES SCHEDUEL SHEET A1.2 FOR ADDITIONAL INFORMATION



DETERMINE THE INCLUSION OR USE OF ANY PARTICULAR ITEM.

EQUIPMENT PLAN KEYNOTES (c) 1 AIR CURTAIN ABOVE SLIDING DOOR TYP. REF. ELECTRICAL SHEETS 13 BUNN WATER HEATER H5X P/N 43600-0026 14 LA MARZOCCO ESSPRESSO MACHINE 2 ELEVATED CUP DISPENSER -MODEL LINEA PB (AV)-3 NOTE: DRAIN LINES FOR EQUIPMENT ON EITHER SIDE OF CUP DISP. ARE NOT TO LA MARZOCCO ESSPRESSO MACHINE MODEL LINEA PB (AV)-4 CROSS CUP DISPENSER. HOLD LINES AS TIGHT AS POSSIBLE TO WALL 16 MAZZER COFFEE BEAN GRINDER – MODEL ROBUR S NERO (a) 3 | BLEND-TECH RAPID RINSER MAZZER DECAF COFFEE BEAN GRINDER -MODEL SUPER JOLLY PRO V (E) NERO 4 BUILT-IN CUP RINSE 17 BUILT-IN KNOCK BOX 5 T&S BRASS RINSE WELL w/ STEM - B-2282-01-F05 (a) TRAULSON UNDERCOUNTER COOLER - CULC-36R-GD 36" (b) 6 NEW MUILTIPURPOSE DRY CHEMICAL (2A:10BC) FIRE EXTINGUISHER (PER NFPA 10) 19 SYRUP RACK 7 NOT USED 20 VITAMIX BLENDER MOD. 036021-1355 8 CUSTOM STAINLESS STEEL 3-COMPARTMENT SINK - RE: PLUMBING DRAWINGS (a) 21 STORAGE RACK: A - SS 12"x 36"x 36" 9 STAINLESS STL. HANDSINK -REF. PLUMB. DRAWINGS B - SS 18"x 90"x 80" (a) 10 2 DOOR REACH-IN COOLER -ATOSA MFC8723GR 54" 22 WATER FILTERING & REVERSE OSMOSIS SYSTEM (d) 11 MANITOWOC ICE MAKER HEADS IYF 1800 C (a) 23 MOBILE ICE-BIN (UNDERCOUNTER) 11A MANITOWOC ICE MAKER BIN LB 1760 60" 24 STAINLESS STL. WORK TABLE 12 SPACEMAN FREEZE MACHINE #6695-C

EQUIPMENT NOTES:


- a. EQUIP. MANUFACTURER IS OPTIONAL BUT MUST BE EQUAL APPROVED BY 7 BREW, U.N.O. b. PROVIDED & INSTALLED ON SITE BY SITE GEN. CONTRACTOR
- c. UNIT TO BE FURNISHED & INSTALLED BY NATIONAL MODULAR (MODULAR BLDG. MANUF.)


d. REMOTE CONDENSER - IF 1800C

EQUIPMENT GENERAL NOTES:

1. ALL EQUIPMENT TO BE INSTALLED BY A LICENSED INSTALLER AND TO

THE MANUFACTURER'S SPECIFICATIONS.





THE DESIGN AND DETAILS
DISCLOSED HEREIN ARE THE
EXCLUSIVE PROPERTY OF
RODGER W. BAKER, AIA AND
SHALL NOT BE COPIED OR
REPRODUCED IN WHOLE OR
IN PART WITHOUT HIS PRIOR
WRITTEN CONSENT. RODGER W. BAKER, AIA

FLOOR FINISHES & FIXTURE


PLANS

DATE 6-14-2024

> DRAWN BY: RC CHECKED BY:


A1.3

SHEET NO.



BAKER DESIGN GROUP, PA
RODGER W BAKER ARCHITECT, AIA NCARB
135 N. Main St. Wichita KS 67202 316.267.7142

7 Brew 5905 Stage Rd. 3ARTLETT, TN. 38133



THE DESIGN AND DETAILS
DISCLOSED HEREIN ARE THE
EXCLUSIVE PROPERTY OF
RODGER W. BAKER, AIA AND
SHALL NOT BE COPIED OR
REPRODUCED IN WHOLE OR
IN PART WITHOUT HIS PRIOR
WRITTEN CONSENT.

RODGER W. BAKER, AIA


EXTERIOR ELEVATIONS

DATE 6-14-2024

RC
CHECKED BY:
RB
SHEET NO.


DRAWN BY:

A3



BAKER DESIGN GROUP, PA
RODGER W BAKER ARCHITECT, AIA NCARB
135 N. Main St. Wichita KS 67202 316,267.7142
rodger@bakerdesigngrouppa.com

/ **БГеW** 5905 Stage Rd. 3ARTLETT, TN. 38133



THE DESIGN AND DETAILS
DISCLOSED HEREIN ARE THE
EXCLUSIVE PROPERTY OF
RODGER W. BAKER, AIA AND
SHALL NOT BE COPIED OR
REPRODUCED IN WHOLE OR
IN PART WITHOUT HIS PRIOR
WRITTEN CONSENT.

RODGER W. BAKER, AIA

REMOTE STORAGE/ COOLER UNIT PLAN & ELEV's

DATE 6-14-2024

DRAWN BY:
RC
CHECKED BY:
RB
SHEET NO.

A8

NEW RETAIL BUILDING

7418 HWY 70 BARTLETT, TN



BAY 1 - 1,500S.F.

BAY 2 - 1,500S.F.

BAY 3 - 1,500S.F.

BAY 4 - 1,500S.F.

TOTAL: 6,000S.F.





Retail Center

7418 Hwy 70

Bartlett, TN 38135

ABBREVIATIONS ANCHOR BOLT AIR CONDITION ACOUSTICAL CEILING TILE ABOVE FINISHED FLOOR ALTERNATE ALUMINUM

ACCESS PANEL ARCHITECTURAL AUTOMATIC BETWEEN BITUMINOUS BEAM(S) BOTTOM BEARING BUILT-UP


CERAMIC CER CONTROL JOINT CENTER LINE CLOSET CLEAR CMU CONCRETE MASONRY UNIT COLUMN COL CONC CONST CONCRETE CONSTRUCTION CONTINUOUS CERAMIC TILE

CONT CTR DETAIL DRINKING FOUNTAIN DECK(ING) DIMENSION DOWEL DOOR DOWNSPOUT DWG DRAWING EACH EXPANSION JOINT

ELECTRICAL EL,ELEV ELEVATION ENTRANCE EQUIP ELECTRIC DRINKING FOUNTAIN EX, EXIST EXISTING EXPANSION EXTERIOR, EXTINGUISHER ELECTRIC WALL HEATER FIRE CODE FLOOR DRAIN FD FOUNDATION FIRE DEPARTMENT CONNECTION FIRE EXTINGUISHER (CABINET) FIXFIXT FIXTURE

FLASH(G) FLASH(ING) FLOOR FLUORESCENT FLUOR FACE OF MASONRY FTG FIRE BLANKET FIBER REINFORCED PLASTIC FIRE HOSE CABINET FIRE RETARDANT TREATMENT GALVANIZED GYPSUM BOARD GALVANIZED METAL GOVERNIMENT GRATING GYP GYPSUM

HT,HGT



VICINITY MAP

HANDICAP




MAS MAX


MECH MEZZ

MR MTD MTL

LOW POINT LINTEL MASONRY MAXIMUM MECHANICAL MEZZANINE MFRMFG MANUFACTURER MINIMUM MISCELLANEOUS MASONRY OPENING MOISTURE RESISTANT

NUMBER NOMINAL





PANEL PAINT PNL PNT POL POLISHED PREFAB PREFABRICATED PROPERTY POUNDS PER SQUARE FOOT POUNDS PER SQUARE INCH PTD PAINTED PVMT PAVEMENT LB(S) POUND(S) RADIUS, RISER


ROOF DRAIN REBAR REINFORCING BAR REFERENCE REG REINF REG RES RET REINFORCING REQUIRED RESILIENT RETAINING REVISION RIGHT HAND ROOM


ROUGH OPENING SHEATHING SIMILAR SPECIFICATION SQUARE STAINLESS STEEL STANDARD STRUCT STRUCTURAL

SUSPENDED THRESHOLD THOLD TELEPHONE TEMPERED THICK(NESS. TREATED TRTD TYPICAL UNDERWRITERS LABORATORY


UNLESS NOTED OTHERWISE VINYL VINYL COMPOSITION TILE VERTICAL VINYL WALL COVERING WITH(OUT)


W/(Ø) WOVEN WIRE FABRIC(MESH) WATER RESISTANT







NORTH ARROW







DETAIL REFERENCE




WINDOW REFERENCE

MATCHLINE


LOCATION OF PROJECT

LEGEND OF SYMBOLS




DRAWING TITLE

ELEVATION



BUILDING OR WALL SECTION



ROOM NAME & NUMBER

DOOR REFERENCE

ELEVATION MARK

GRID REFERENCE

DOOR AND WINDOW DETAILS

FOUNDATION PLAN **ROOF FRAMING FOUNDATION DETAILS**

MECHANICAL

MECHANICAL SEISMIC NOTES, SPECIFICATIONS FLOOR PLAN - MECHANICAL

PROJECT INFORMATION

PROJECT DESCRIPTION: Business space made available for rent (white box) in an existing facility. Adjacent tenant spaces are I-Hour

APPLICABLE CODES:

2021 International Building Code 2021 International Energy Conservation Code 2021 International Mechanical Code 2021 International Fuel Gas Code 2021 International Plumbing Code 2020 National Electric Code 2010 ADA Standards for Accessible Design ANSI ICC 117.1 (Current version)

BUILDING INFORMATION

OCCUPANCY TYPE **BUSINESS** CONSTRUCTION TYPE **VB, SPRINKLERED** TOTAL BUILDING AREA 6,566 S.F. 1,527 S.F. Tenant Space

BUILDING HEIGHT 16'-0" NUMBER OF FLOORS I (one) AUTOMATIC FIRE SPRINKLER

GENERAL NOTES

1. Verify conditions, dimensions and elevations of site and services.

and shall be resolved prior to proceeding with the work.

2.All Dimensions and conditions tieing into or governed by existing construction are approximate and are not guaranteed to be correct. All such dimensions and conditions shall be field verified by the general contractor prior to the preparation of shop drawings and before proceeding with any work. The first submittal of shop drawings must contain correct conditions and dimensions obtained from the field. If conditions and dimensions vary greatly from those shown, the contractor shall notify the architect before preparation of shop drawings or before proceeding with work. Where dimensions are shown, use dimensions, do not scale. Where dimensions are shown, use exact dimensions - Dimensions with + indication only are adjustable

3. Contractor shall coordinate and obtain all necessary permits and approvals or guidelines from governing regulatory agencies before proceeding with any items of work under or within such jurisdictions.

4.All work shall conform to the requirements of the 2021 International Building Code. And all federal, state and city laws, codes and regulations as each may apply.

5.General notes and typical details shall apply to all parts of the project except where they conflict with specific notes and details where conditions are not specifically indicated, but are of similar character to details shown, similar details shall be used. Subject to the review of the

6.Omissions or conflicts between the various elements of the working drawings and/or specifications shall be brought to the attention of the architect prior to the stage of such work. 7. The contractor shall be responsible for coordinating the schedule and work of all trades and shall check all dimensions, all discrepancies shall be called to the attention of the architect

8.To establish the complete scope of its work and to affect close coordination with the other trades, each trade shall completely review the plans and specifications, not only for its respective trade but for the work of all other trades as well. Titles of divisions (and sections in specifications) are provided merely for convenience and shall not be taken as an absolute segregation of the units of material and labor.

9. The contract drawings and specifications represent the finished structure and do not indicate the method of construction. The contractor shall supervise and direct the work and shall be solely responsible for construction means and methods. Sequences and procedures including, but not limited to, bracing and shoring.

10. The contractor agrees that in accordance with generally accepted construction practices the contractor shall assume sole and complete responsibility for the job site conditions during the course of construction including the safety of all persons and property and that this requirement shall apply continuously and not be limited to normal working hours.

II.All work shall be performed in a thoroughly first class and workmantile manner in conformity with the plans and specifications and shall be in good usable condition at the completion of the project.

12. Coordinate floor and wall openings with all trades involved. Provide steel frames, sleeves, lintels, and similar enclosures required around penetrations in masonry or concrete walls or floors. Fire seal penetrations through fire resistive rated construction.

INDEX OF DRAWINGS

COVER

SHT I OF 7 CIVIL COVER SHEET SHT 2 OF 7 SITE PLAN SHT 3 OF 7 SANITARY SEWER PLAN SHT 4 OF 7 EROSION CONTROL PLAN **GRADING & DRAINAGE PLAN**

LANDSCAPE PLAN

ACCESSIBILITY PLAN

OVERALL FLOOR PLAN **EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS** WALL SECTIONS WALL SECTIONS **ROOF PLAN ROOF DETAILS** DOOR AND WINDOW KEY PLAN DOOR AND WINDOW ELEVATIONS

LIFE SAFETY PLAN

STRUCTURAL

GENERAL NOTES/ ABBREVIATIONS ROOF/ WALL DETAILS

PLUMBING DETAILS, SPECIFICATIONS FLOOR PLAN - PLUMBING


ELECTRICAL

SCHEDULES - ELECTRICAL E002 ONE LINE - ELECTRICAL E003 PANELBOARDS & EQUIPMENT SCHEDULES - ELECTRICAL E004 NOTES - ELECTRICAL E100

PHOTOMETRICS - ELECTRICAL EIOI PHOTOMETRICS - ELECTRICAL PHOTOMETRICS - ELECTRICAL E102 E201 FLOOR PLAN - ELECTRICAL

REVISIONS


uild



PROJECT NUMBER

AS SHOWN SHEET NUMBER DATE OF ORIGINAL ISSUE

June 9, 2024



SCHEDULE OF DRAWINGS

COVER PAGE	1
SITE PLAN	2
SANITARY SEWER PLAN	3
EROSION CONTROL PLAN	4
GRADING AND DRAINAGE	5
LANDSCAPE PLAN (BY OTHERS)	6
ELEVATIONS (BY OTHERS)	7

SITE PLAN APPLICATION

7418 U.S. HIGHWAY 70

BARTLETT, TENNESSEE

National Cities Corp I, LP. DEVELOPER

The Bray Firm ENGINEER


GENERAL NOTES


CONSTRUCTION NOTES:


SAID DRIVES AND YARDS.


1. PROPERTY LINES SHALL BE FIELD VERIFIED PRIOR TO CONSTRUCTION. GRADING, CLEARING AND THE ERECTION OR REMOVAL OF FENCES ALONG PROPERTY LINES SHALL BE FULLY COORDINATED WITH ADJACENT PROPERTY 2. THE CONTRACTOR SHALL VERIFY ANY EXISTING DATA AND REPORT ANY SIGNIFICANT DISCREPANCIES TO THE ENGINEER. 3. THE CONTRACTOR SHALL NOT ENTER UPON, WORK UPON NOR CAUSE DAMAGE TO ANY ADJACENT PROPERTIES WITHOUT PRIOR PERMISSION FROM SAID PROPERTY OWNER. 4. LOCATION OF EXISTING UNDERGROUND UTILITIES ARE APPROXIMATE AND ARE NOT NECESSARILY ALL OF SAME, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE APPROPRIATE UTILITY COMPANY TO DETERMINE THE EXACT LOCATION OF ALL UTILITIES AND/OR UNDERGROUND STRUCTURES PRIOR TO THE INITIATION OF ANY CONSTRUCTION. CONTRACTOR SHALL ALSO ASSUME FULL RESPONSIBILITY FOR DAMAGE TO ANY EXISTING UTILITIES ENCOUNTERED WITHIN THE CONSTRUCTION PERIMETERS. FOR SITE LOCATION OF EXISTING UTILITIES INVOLVING M.L.G.&W., SOUTH CENTRAL BELL, AND/OR TEXAS GAS COMPANY, PLEASE CALL 1-800-351-1111. FOR SEWER SERVICE LOCATIONS, CALL 385-6499. 5. CONTRACTOR SHALL MAINTAIN ACCESS TO ALL PROPERTIES. 6. TYPICAL SIDE SLOPES TO BE 1 FOOT VERTICAL TO 4 FEET HORIZONTAL.
7. ALL AREAS IN CUT OR FILL WHERE VEGETATION HAS BEEN REMOVED SHALL BE SEEDED, MULCHED, FERTILIZED, AND/OR SODDED AS REQUIRED TO PREVENT EROSION. 8. 24 HOURS PRIOR TO ANY CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE CITY OF BARTLETT ENGINEER'S OFFICE AT 385-6499.
9. ALL CONSTRUCTION MATERIALS & PROCEDURES SHALL MEET STANDARD CITY OF BARTLETT SPECIFICATIONS. 10. ALL FILL AND/OR TRENCH BACKFILL SHALL BE COMPACTED (IN 6 INCH LIFTS) TO 95% STANDARD PROCTOR WITHIN 3% OF OPTIMUM MOISTURE CONTENT AS DETERMINED BY ASTM D698-78 LATEST REVISION (STANDARD PROCTOR).


11. THE CONTRACTOR SHALL INSTALL AND MAINTAIN A SILT FENCE PARALLELED WITH HAY BALES AT THE TOP OF ALL DITCH BANKS FOR THE WIDTH OF THE CONSTRUCTION LIMITS AND CONTINUOUSLY ALONG THE "STREAMSIDE" CONSTRUCTION LIMIT. 12. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN EROSION CONTROL DURING CONSTRUCTION BY THE PLACEMENT OF SILT FENCES AND HAY BALES WHERE NECESSARY TO PREVENT DOWNSTREAM SILTATION OF ANY DITCHES, PIPES, DRAINAGE STRUCTURES OR ADJACENT PROPERTIES. THE CONTRACTOR SHALL PROVIDE ANY ADDITIONAL EROSION CONTROL AS NEEDED OR AS DIRECTED BY THE ENGINEER. 13. CONTRACTOR SHALL PROVIDE ALL NECESSARY EROSION CONTROL METHODS AS PER THE CITY OF BARTLETT, SHELBY COUNTY, AND STATE OF TENNESSEE REGULATIONS. 14. ENGINEERS CERTIFICATE: THIS PROJECT HAS BEEN DESIGNED IN ACCORDANCE WITH THE CITY OF BARTLETT SUBDIVISION REGULATIONS AND SPECIFICATIONS. 15. LOT GRADING AND DRAINAGE: FINISH GRADE SHALL BE SLOPED AWAY FROM THE FOUNDATION FOR DRAINAGE. THE FINISH GRADE MUST BEGIN AT LEAST 10 INCHES BELOW THE TOP OF THE FOUNDATION WALL OR THE GRADE OF THE CONCRETE SLAB AND FOUNDATION. THE MINIMUM GRADE AWAY FROM THE FOUNDATION WALL SHALL BE AT LEAST 5 PERCENT IN ALL DIRECTIONS. THE DRIVEWAY SHALL BE SLOPED DOWN AT 2 PERCENT FOR AT LEAST 8 FEET FROM THE STRUCTURE. 16. THE CITY OF BARTLETT SHALL HAVE INGRESS/EGRESS RIGHT TO USE PRIVATE DRIVES AND YARDS FOR THE PURPOSE OF MAINTAINING ALL PUBLIC UTILITIES AND SHALL BEAR NO RESPONSIBILITY FOR THE MAINTENANCE OF














PLUMBING SUMMARY

PLUMBING REQUIRED:

TOTAL OCCUPANCY

WATER CLOSET:

= 10 people (1,5146F/150) (TENANT SPACE)

24 FEMALE - 1 WATER CLOSET PER 25 WATER CLOSET: FOR THE FIRST 50 AND 1 PER 50 FOR

THE REMAINDER EXCEEDING 50 = 1WATER CLOSETS REQUIRED

24 MALE = 1 WATER CLOSET PER 25 FOR THE FIRST 50 AND 1 PER 50 FOR THE REMAINDER EXCEEDING 50 = 1

WATER CLOSETS REQUIRED

HAND SINKS: 1/25 for the first 50 + 1/50 for the

remainder

DRINKING FOUNTAINS: 1 REQUIRED 1 PROVIDED

1 REQUIRED MOP SINK: 1 PROVIDED

NOTE: LEAVE 10' OF CONCRETE UN-POURED UNTIL TENANT LEASE SIGNED AND RE-POUR SLAB AS

PARTITION LEGEND

(2) 6" WOOD STUD WALLS. I HOUR INTERIOR NON-LOAD BEARING PARTITION EQUAL TO U.L. DESIGN NO. U419. CONSTRUCTED OF (1) ONE LAYER OF 5/8" TYPE 'X' GYPSUM BOARD ON EACH SIDE OF WOOD STUD FRAMING TIGHT FROM FLOOR SLAB TO

NOTE: RATED WALLS WILL BE COMPLETED AS TENANT LEASES ARE SECURED AND PRIOR TO MOVING IN.

EXIT ARRANGEMENT

- 2 EXITS ARE REQUIRED PER IBC 2021 TABLE 1006.2.1 3 EXITS ARE PROVIDED.
- EXITS SHALL BE SEPARATED BY NO LESS THAN 1/3 THE DIAGONAL OF THE AREA
- EXCEPTION 2. (DIA DIST.= 124'-Ø") THE MINIMUM DISTANCE BETWEEN EXITS MUST

BE 42'-0" THE ACTUAL DISTANCE IS 41'-4"

SERVED PER IBC 2015 SECTION 1007.1.1


RATED WALL STENCILING EXAMPLE

EXAMPLE: (TEXT HEIGHT 3" MINIMUM)

FIRE AND/OR SMOKE BARRIER -PROTECT ALL OPENINGS

1. FIRE PARTITIONS, OR ANY OTHER WALL REQUIRED TO HAVE PROTECTED OPENINGS OR PENETRATIONS SHALL BE EFFECTIVELY AND PERMANENTLY IDENTIFIED WITH SIGNS OR STENCILING. SUCH IDENTIFICATION SHALL:

- BE LOCATED IN ACCESSIBLE CONCEALED FLOOR,
- FLOOR-CEILING OR ATTIC SPACES. 1.2. BE LOCATED WITHIN 15 FEET(4572MM) OF THE END OF EACH WALL
- AND AT INTERVALS NOT EXCEEDING 30 FEET (9144 MM) MEASURED HORIZONTALLY ALONG THE WALL OR PARTITION, AND 1.3. INCLUDE LETTERING NOT LESS THAN 3 INCHES (76 MM) IN HEIGHT
- WITH A MINIMUM 3/8" STROKE IN A CONTRASTING COLOR INCORPORATING THE SUGGESTED WORDING: "FIRE AND/OR SMOKE BARRIER-PROTECT ALL OPENINGS" OR OTHER WORDING.





REVISIONS




SHEET NUMBER

DATE OF ORIGINAL ISSUE June 9, 2024







HESE DRAWINGS AND SPECIFICATIONS ARE OWNED AND DPYRIGHTED BY GUY PAYNE & ASSOCIATES ARCHITECTS C. AND MAY NOT BE USED, COPIED, OR DUPLICATED THOUT PRIOR WRITTEN CONSENT. ANY UNAUTHORIZED US DISCLOSURE OF THE PROPRIETARY INFORMATION DINTAINED HEREIN MAY SUBJECT SUCH PERSONS TO RIMINAL AND CIVIL PENALTIES AND DAMAGES.

STE. 114
STE 38018

CONTAIN
CRIMINAL


879 WILLOW CIRCLE, STE. 114 CORDOVA, TENNESSEE 38018

Retail Building



REVISIONS


No. Date



SCALE
AS SHOWN
SHEET NUMBER


AS 1.1


OF
DATE OF ORIGINAL ISSUE
June 9, 2024






AS SHOWN SHEET NUMBER **AS1.2** DATE OF ORIGINAL ISSUE June 9, 2024






June 9, 2024







PROJECT NUMBER
42/02
SCALE
AS SHOWN
SHEET NUMBER

DATE OF ORIGINAL ISSUE June 9, 2024







BRICK SOLDIER

BRICK DETAIL - SEE 1/A4.1 METAL PARAPET


ALUMINUM STOREFRONT ALUMINUM DOOR

ALUMINUM TRANSACTION WINDOW , SEE DETAIL A/A6.00 HOLLOW METAL DOOR

PRE-FABRICATED METAL DOWNSPOUT

METAL CANOPY PRE-FABRICATED METAL GUTTER

EXTERIOR LIGHTING - SEE ELECTRICAL EXTERIOR SIGNAGE - SEE ELECTRICAL FOR POWER REQUIREMENTS



REVISIONS						
No.	Date					


PAYNE

Retail Building
7418 Hwy 70
Bartlett, TN





PROJECT NUMBER
42/02
SCALE
AS SHOWN
SHEET NUMBER DATE OF ORIGINAL ISSUE


June 9, 2024


























ARCHITECTS

ASSOCIATES




PROJECT NUMBER
4202
SCALE
AS SHOWN
SHEET NUMBER

A 1

OF
DATE OF ORIGINAL ISSUE

June 9, 2024



DOOR DATA

STYLE: Aluminum door

FRAME: Aluminum

GLAZING: Yes

HARDWARE: Lockset, Push/Pull,


Closer, Flush Bolt, Thumb Lock,

Weatherstrip

RATING: N/A

QUANTITY: 4

DETAIL: 1/6.2



DOOR DATA

STYLE: Hollow Metal

FRAME: Hollow Metal

GLAZING: No

HARDWARE: Lockset, Push/Pull,

Closer, Flush Bolt, Thumb Lock,

Weatherstrip, Panic


Hardware RATING: N/A

QUANTITY: 4


DETAIL: 2/6.2

Door Elevation

SCALE: 1" = 1'-0"




(A-) FIXED ALUMINUM STORE FRONT FRAMING DETAIL: 3/6.2





project number 42Ø2 AS SHOWN SHEET NUMBER DATE OF ORIGINAL ISSUE June 9, 2024



<u>Abbreviations</u> Above Finished Floor Arch Architectural Bldg BTM Bottom Brg Bearing Centerline Clear or Clearance CMU Concrete Masonry Unit Col Column Conc Concrete Conn Connection Const Construction Cont Continuous Dia, Ø Dimension Dwg Drawing Each Face Elec Electrical Elev Elevation Embed Embedment EW Each Way Exist Existing Exp Expansion Ext Exterior Fnd Foundation FFE Finished Floor Elevation Full Penetration Far Side Ftg Footing Gage or Gauge Horiz Interior Kips(1000 LBS.) KSI Kips per Square Inch LB, # Pound Live Load LLH Long Leg Horizontal LLV Long Leg Vertical Long Longitudinal Manuf Manufacture Max Mech Mechanical Mid Middle Min Minimum Misc Miscellaneous N/A Not Applicable Near Side NTS Not to Scale On Center Орр Opposite Perp Perpendicular Pre-engineered Metal Building PEMB Pounds per Square Foot PSI Pounds per Square Inch Reinf Reinforcing(-ed, -ment) Req'd Rev Required Revision RW Sched Sect Retaining Wall Schedule(d) Section Sim Similar Spec Specifications(s) Sym Symmetrical Top, Tension T/, T.O. Top of T/Conc Top of Concrete T/Ftg T/Slab Top of Footing Top of Slab T&B Top & Bottom Temp Thk Temperature Thickness TOS Top of Steel TOW Top of Wall Trnv Transverse Тур UNO Vert Unless Noted Otherwise Vertical w/ With w/o Without W.W.F. Welded Wire Fabric Legend / Symbols Column Grid Lines View Name 1/8" = 1'-0" Detail / Section Number

Design Critoria

<u>Design Criteria</u>	
Building Code	Seismic loads (Per ASCE 7-16):
-2018 International Building Code (IBC)	-Occupancy CategoryII -Spectral Response Coefficients S _s = 0.732
Roof Loads:	$S_1 = 0.269$
-Live Load20 psf	$S_{ds} = 0.592$
-Dead Load25 psf	$S_{d1} = 0.370$
·	-Soil Site ClassD
Snow Load:	-Seismic Design CategoryD -Response modification factor6.5
Ground Snow Load: Pg = 10 psf	-Delfection amplification factor3.0
3	-System overstrength factor4.0
Wind Load (Per ASCE 7-16):	-Seismic force resisiting systemPlywood Shear Walls
-Ultimate Wind Speed = 105 mph	-Design base shearV= CsW
-Risk Category II -Wind ExposureB	-Analysis procedureEquivalent Lateral Force

Shallow Foundations

1. Foundations are designed based upon assumed soil bearing capacities as stated below.

2. Allowable soil bearing pressures used in design: Spread footings =1800 psf /Continuous footing = 1800 psf

3. Footing excavations shall be observed and tested by an experienced geotechnical engineer prior to steel or concrete placement in order to assess that the foundation materials are consistent with above stated assumed soil bearing

4. In the event that the soils test results are disapproved, footing excavations shall be undercut (under the direction of the soils engineer) until soils of adequate bearding capacity are encountered. Backfill under footings shall consist of concrete f'c = 2500 psi @ 28 days placed up to the proposed bottom of footing elevation.

5. Footings shall bear on undisturbed residual soils or compacted fill, maximum desnist of 98% ASTM D-698.

6. Footing elevations shown on the plans are for estimating purposes only. Actual footing elevations shall be determined by the contractor at the site and shall be a minimum of 12" below finished grade.

7. All water shall be removed from foundation excavations prior to placing of concrete. If bottoms of trenches become softened due to water before footings are cast, the contractor, at his own expense, shall excavate the softened material and replace with concrete.

8. All pipes (water lines, sewer lines, etc.) And conduits running through walls / slabs shall be protected with ½"

9. Continuous footing perpendicular to pipe runs shall be either lowered to allow pipes to pass through above such footings or have concrete jacket if pipes are low enough to be placed below such footings. Footings parallel to pipe runs shall be lowered to avoid surcharge onto the trench excavations.

General Notes

1. No provision of any referenced standard specification, manual or code (whether or not specifically incorporated by reference in the contract documents) shall be effective to change the duties and responsibilities of the owner, contractor, architect, engineer, supplier, or any of the consultants, agents, or employees from those set forth in the contract documents, nor shall it be effective to assign to the structural engineer of record (S.E.R.) or any of the S.E.R.'s consultants, agents, or employees any duty or authority to supervise or direct the furnishing or performance of the work or any duty or authority to undertake responsibilities contrary to the provisions of the contract documents.

2. Reference to standard specifications (concerning structural design) of any technical society, organization, or association or to codes of local or state authorities, shall mean the latest standard codes, specification or tentative specification adopted at the date of taking bids, unless specifically stated otherwise.

3. In the event contract documents conflict with the code of practice or specifications of ACI, PCI, AISC, AISI, SJI or other standards, contact structural engineer for clarification.

4. Notes and specific details on the drawings shall take precedence over general structural notes and typical details. Contact the architect / engineer for a determination of intent before proceeding with related work if there is any

5. Material, workmanship, and design shall conform to the referenced building code.

6. The contractor shall verify the dimensions, elevations and site conditions before starting work. The architect / engineer shall be notified of any discrepancy.

7. The design, adequacy, and safety of erection bracing, shoring, temporary supports, etc. is the sole responsibility of

8. The contractor shall coordinate the architectural, mechanical, electrical, plumbing and civil works with the structural contract documents. The architect / engineer shall be notified of any discrepancies or omissions.

9. The contractor shall notify, in writing, the engineer of conditions encountered in the field that are contradictory to those shown on the contract documents.

10. For dimensions not shown on the structural drawings see the architectural drawings.

Structural Steel

1. Structural steel shall conform to: W-Shapes = A992 Pipe columns = ASTM A53 type E or S Grade B. HSS = ASTM A500 Grade B.

Plates, Channels, Angles, Misc, etc. = A36

2. Design, fabrication, and erection shall be in accordance with aisc specification for the design, fabrication, and

erection of structural steel buildings.

3. Structural steel shall be detailed in accordance with standard practices of AISC a. Connections: AISC Manual standard connections, unless noted. b. High-strength bolts: ASTM A325 bearing type N installed in accordance with "specification for structural joints Using ASTM A325 or A490 Bolts", research council on riveted and bolted structural joints.

4. All welds must be made in accordance with the American Welding Society Code D-1.1. 5. Field and shop connections shall be welded as shown on drawings or bolted with high strength bolts, unless noted

6. See architectural drawings for angles, clips, bars, plates, and other items attached to structural members, and for chamfers on concrete walls, beams, etc.

7. Provide temporary bracing as required to maintain alignment and security of structures during construction.

8. Do no cutting, drilling or modifying of structural members without the approval of the engineer.

9. The manufacturer's name, brand or trademark (mill identification marks) shall be shown in raised letters at intervals along the length. (ASTM A6/A6M 96-97, paragraph 12.2) note: small shapes with the greatest crosssectional dimension not greater.

Concrete

1. All phases of work pertaining to the concrete construction shall conform to the "Building Code Requirements for Structural Concrete" (ACI 318), latest edition with modifications as noted in the drawings or specifications.

2. Concrete mixes shall be designed by a qualified testing laboratory and approved by the structural engineer.

3. All exposed corners or edges of columns, piers, walls, etc., shall be formed with a 3/4" chamfer unless noted otherwise on

structural or architectural drawings.

4. All reinforcing bars, anchor bolts and other concrete inserts shall be well secured in position prior to placing concrete. 5. Provide sleeves for plumbing and electrical openings in concrete before placing concrete. Do not cut any reinforcing that may conflict. Coring is not permitted except as shown. Notify the structural engineer in advance of conditions not shown on the drawings.

6. Conduit or pipe size (o.d.) shall not exceed 30% of the slab thickness and shall be placed between the top and bottom reinforcing unless specifically detailed otherwise. Concentrations of conduits or pipes shall be avoided except where detailed

7. Curing compounds on concrete that is to receive special finish shall be approved by the manufacturer before use. 8. Roughen surface of horizontal or nearly horizontal construction joints so that the aggregate shall be exposed uniformly,

leaving no laitance, loosed particles or damaged concrete.

9. Locate joints not indicated to least impair strength and appearance of the structure. Locate horizontal joints in concrete only where they normally occur or where indicated. Locate vertical joints in middle third of spans of slabs, beams, or girders unless a beam intersects a girder at middle location, in which case offset joints in girders twice the width of the beam.

10. Once formwork has been removed from concrete retaining walls, brace walls thoroughly before placing soil against wall and keep bracing in place for a minimum of 7 days after earthwork is complete.

	ncrete Strength	_				
Use (Location)	28 Day Strength	Aggregate Size (Max.)	Cement/CY (Min.)	W/C ratio (Max.)	Slump (Max.)	Air Entrainment
Slab-on-grade (Interior)	f'c=3,000 psi	1"	480#	.62	4-1/2"	None
Exposed Concrete	f'c=4,000 psi	1"	560#	.54	4-1/2"	4%-6%
Footings	f'c=3,000 psi	1"	480#	.62	4-1/2"	None

Fy = 60 ksi

2. Ld = Straight Bar Development Length

3. Ldh = Development Lengh w/ Standard Hook.

1. Reinforcing shall be detailed and placed in conformance with ACI Detailing Manual.

2. Reinforcing bars shall conform to the requirements of ASTM A615 Grade 60 except all reinforcing in concrete moment frames and shear walls and all welded reinforcement shall conform to ASTM A706 Grade 60.

3. Welded wire fabric shall conform to ASTM A185.

2. All cement shall be Portland Cement Type 1

4. Minimum lap of welded wire fabric shall be 6" or one full mesh + 2", whichever is greater.

5. Dowels between footings and walls shall be the grade, size and spacing or number as the vertical reinforcing, respectively.


6. Reinforcing steel in all concrete walls and footings shall be continuous around corners.

7. Provide (2) #5 extra reinforcing bars around all side of openings in concrete, unless noted otherwise on the plans. Extend bars 2'-0" beyond each edge of opening.

8. Minimum clear coverage of concrete over reinforcement shall be: a. Concrete cast against and permanently exposed to earth ... b. Concrete exposed to earth or weather: i. No. 6 through no. 18 bar.... ii. No. 5 bar, w31 or d31 wire or smaller... c. Concrete not exposed to weather or in contact with ground: i. Slabs walls and joists no. 14 & no. 18... ii. Slabs walls and joists no. 11 & smaller.

REINFORCING EMBEDMENT / DEVELOPMENT LENGTH							
	f'c = 30	00 PSI	f'c = 40	00 PSI	f'c = 5000 PSI		
Bar Size	Ld	Ldh	Ld	Ldh	Ld	Ldh	
#3	16 1/2"	8 1/2"	14 1/2"	8"	13"	7"	
#4	22"	11"	19"	10"	17"	9"	
#5	28"	14"	24"	12"	22"	11"	
#6	33"	17"	29"	15"	26"	13"	
#7	48"	20"	42"	17"	38"	15"	
#8	55"	22"	48"	19"	43"	17"	
#9	62"	25"	54"	22"	48"	20"	
#10	70"	28"	61"	25"	54"	22"	
#11	78"	31"	67"	27"	60"	24"	

iii.Beams, columns: ties and primary reinforcing......1-1/2"



Plywood Sheathing

1. Plywood shall be interior type with exterior glue conforming to PS-1 of grade as specified, laid with face grain perpendicular to supports. Use common nails only unless otherwise approved by the structural engineer and local building official. All plywood shall be 5 ply material.

a. Roof sheathing: 5/8" CDX plywood sheathing, Pll 24/0 or better, with 8d nails (common or box) at 6" o.c. at support edges, and at 12" o.c. at intermediate members. b. Floor sheathing: 3/4" T&G Plywood, Glued & Screwed at 6" o.c. at support edges, and at 12" o.c. at

intermediate members. c. Shear walls: Plywood grade to be either structural I or CDX or OSB. Reference shear wall schedule for specified grade and thickness.

2. All plywood sheathing at floor, walls and roof shall be inspected and approved by building inspector, where required, prior to covering with flooring or roofing material.

3. Solid blocking at edges required for plywood only where called for on drawings.

1. Wood structures have been designed in accordance with the National Design Specifications for Wood Construction by the National Forest Products Association.

2. All dimensional lumber shall be No. 2 Southern Pine kiln dried to 19% maximum moisture content with allowable stress values of 1200 psi in bending and a modulus of elasticity of 1600ksi.

3. All laminated veneer lumber (LVL) shall have a grade equivalent to or better than 2.0E with an allowable

stress value equal to 2900 psi in bending and a modulus of elasticity of 2000ksi.

4. Structural glued-laminated timber shall conform to A.I.T.C. 117 and shall have allowable stress values of 24F combination in Southern Pine.

5. Use light gauge galvanized steel joist hangers and framing anchors, sized for the full load capacity of the supported members (U.N.O.). All wood connectors specified in the drawings shall be manufactured by Simpson Strong-Tie Co., or equal, (U.N.O.)

6. Pressure treat all wood products in direct contact with the foundation.

7. Provide double studs on each side of all openings and all wall ends and triple studs at beam bearings, (U.N.O.)

8. Provide solid blocking under posts, multiple studs or beam bearing locations.

9. Where plywood fillers are required in beams they shall be continuous pieces for the length of the opening and shall be nailed to the 2x members with (2) rows of 10d nails at 12"o.c. Staggered. All top loaded built-up beams shall have their individual pieces fastened together with a minimum of (2) rows of 16d nails at 12"o.c. (U.N.O.)

10. All nailing shall be done in accordance wit the minimum requirements of the local building code, except as otherwise shown, and shall be done with common wire nails.

11. Bolts shall be unfinished A307 with bolt holes through the wood drilled no more than 1/16" greater than the bolt diameter.

Pre-Engineered Wood Trusses

1. All pre-engineered wood trusses shall be designed, detailed and fabricated in accordance with the procedures and requirements outlined in the latest edition of the National Design Specifications for Wood Construction, Truss Plate Institute's (TPI) and the National Design Standard for Metal Plate Connected Wood Truss Construction. All handling, installation and bracing to in accordance with TPI's H1B-91.

2. See design criteria for wind speed, seismic criteria and snow loads.

Dead Load (min.): Top chord = 20 psf / btm chord = 5psf Live Load (min.): Top chord = 20 psf.

3. Pre-engineered wood trusses shall be designed and detailed to fit the dimensions and loads indicated. All design shall be in accordance with allowable values and section properties assigned and approved by a licensed professional engineer and are to be submitted tot the architect / engineer for approval.


4. Permanent bridging / bracing perpendicular to the span of the trusses shall be provided as required by the

5. Truss manufacturer shall provide bracing for the bottom chord of roof trusses for uplift loading conditions.

6. Submit roof valley member sizes, framing details and connections.

7. Truss manufacturer to shop drawings of wood trusses signed and sealed by a professional engineered registered in the state of this project, prior to fabrication. Shop drawings shall include design and engineering data, truss profiles for each truss, a truss placement layout plan, species and stress grade of lumber to be used, details of connectors at all joints, typical connection and anchorage details and all temporary and permanent

8. Gable end design shall include vertical loads imposed including "X" bracing.







Engineering 401 Redfield Dr. Jackson, TN 38305 jeremy@scallionstructural.com

SCALE AS SHOWN DATE OF ORIGINAL ISSUE 5/31/2024


S5.0 Framing Sections







PROJECT NUMBER
4202
SCALE
AS SHOWN
SHEET NUMBER S2.0





PROJECT NUMBER
4202
SCALE
AS SHOWN
SHEET NUMBER


S3.0
OF
DATE OF ORIGINAL ISSUE
5/31/2024

REVISIONS

No. Date

PAYNE & ASSOCIATES ARCHITECTS
879 WILLOW CIRCLE, STE. 114
CORDOVA, TENNESSEE 38018

Retail Building
7418 Hwy 70
Bartlett, TN



A Typical Shear Wall Hold Down
3/4" = 1'-0"

Shearwall Detail
3/8" = 1'-0"

B Typ. Wall Stud Pipe Penetration Detail

AGRICULTURE

AGRICULTURE

OF TENNING

104890

OF TENNING

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

104890

1048

Scallion
Structural
Engineering
401 Redfield Dr.
Jackson, TN 38305
731.217.1614
jeremy@scallionstructural.com
SSE #24-028

PROJECT NUMBER
4202


SCALE
AS SHOWN

SHEET NUMBER

S4.0


OF


DATE OF ORIGINAL ISSUE
5/31/2024



SCALE AS SHOWN SHEET NUMBER S5.0 DATE OF ORIGINAL ISSUE 5/31/2024

SSE #24-028





- REFER TO LOCAL ADOPTED INTERNATIONAL BUILDING CODE.
- SEISMIC RESTRAINTS SHALL NOT BE REQUIRED FOR THE FOLLOWING INSTALLATIONS:
 - PIPING IN MECHANICAL ROOMS (EXCEPT GAS PIPING) LESS THAN 1-1/4 INCH INSIDE DIAMETER
- ALL OTHER PIPING (EXCEPT GAS PIPING) LESS THAN 2-1/2 INCH INSIDE DIAMETER.
- C. ALL RECTANGULAR DUCTS LESS THAN 6 SQ. FT. IN CROSS-SECTIONAL AREA.
- D. ALL ROUND DUCTS LESS THAN 28 INCHES IN DIAMETER.
- ALL PIPING SUSPENDED BY INDIVIDUAL HANGERS 12 INCHES OR LESS IN LENGTH FROM THE TOP OF THE PIPE TO THE BOTTOM OF THE SUPPORT FOR THE HANGER.
- ALL DUCTS SUSPENDED BY HANGERS 12 INCHES OR LESS IN LENGTH FROM THE TOP OF THE DUCT TO THE BOTTOM OF THE SUPPORT FOR THE HANGER.

2 Seismic Notes - Mechanical

- 1. FURNISH AND INSTALL ALL NECESSARY LABOR AND MATERIALS FOR A COMPLETE SYSTEM. ANY APPLIANCES OR MATERIALS OBVIOUSLY A PART OF THE SYSTEM AND NECESSARY FOR ITS PROPER OPERATION, ALTHOUGH NOT SPECIFICALLY MENTIONED HEREIN, SHALL BE FURNISHED AND INSTALLED AS IF CALLED FOR IN DETAIL.
- 2. WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH ALL STATE AND LOCAL CODES.
- 3. ATTAIN AND PAY FOR ALL REQUIRED PERMITS AND FEES.
- 4. DRAWINGS ARE GENERALLY DIAGRAMMATIC AND DO NOT NECESSARILY SHOW FITTING AND DETAIL. INSTALL DUCTS, EQUIPMENT, PIPING, ETC., IN A NEAT WORKMANLIKE MANNER, AND IN ACCORDANCE WITH GOOD PRACTICE FOR A COMPLETE WORKABLE INSTALLATION. AVOID CONFLICT WITH OTHER WORK; MAKE ADEQUATE PROVISIONS FOR PREVENTING NOISE AND VIBRATION. ARRANGE EQUIPMENT INTO THE AVAILABLE SPACE IN A MANNER TO MAKE ALL WORKING PARTS ACCESSIBLE FOR MAINTENANCE AND SERVICE.
- 5. MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED AGAINST DEFECTS FOR ONE
- 6. PROTECT ALL MATERIALS AND EQUIPMENT FROM DAMAGE.
- 7. CONSTRUCT AIR DUCTS IN ACCORDANCE WITH SMACNA DUCT MANUALS LATEST
- 8. HVAC WORK INDICATED DIAGRAMATICALLY, EXACT LOCATION OF ALL COMPONENTS ARE TO BE DETERMINED IN THE FIELD AND BY THE ACTUAL BUILDING CONDITIONS. 9. ALL WORK SHALL BE COORDINATED WITH ALL OTHER TRADES BEFORE ANY
- INSTALLATION IS MADE. 10. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH STATE CODES, MANUFACTURER'S APPROVED PUBLISHED LITERATURE, AND AUTHORITIES HAVING
- JURISDICTION. 11. INSTALLATION OF ALL EQUIPMENT SHALL PERMIT ACCESSIBILITY FOR SERVICE AND/OR
- REPLACEMENT. 12. COORDINATE VOLTAGE AND PHASE OF EACH PIECE OF EQUIPMENT WITH ELECTRICAL
- CONTRACTOR BEFORE ORDERING. 13. FLEXIBLE DUCT RUNOUTS TO CEILING DIFFUSERS SHALL BE INSTALLED FREE OF KINKS
- AND SAGS. MAXIMUM LENGTH OF FLEXIBLE DUCT SHALL BE 3'-0". 14. COMPLETION AND TESTS SHALL INCLUDE CLEANING AND LUBRICATION OF ALL EQUIPMENT, AND ADJUSTMENTS FOR PROPER OPERATION. ADJUST DAMPERS REGISTERS AND DIFFUSERS FOR PROPER AIR DISTRIBUTION. CHECK SYSTEM UNDER ACTUAL OPERATING CONDITIONS AND MAKE ADJUSTMENTS FOR A UNIFORM
- TEMPERATURE THROUGH THE CONDITIONED SPACE. 15. LOCATIONS SHOWN FOR EQUIPMENT ARE APPROXIMATE LOCATIONS. CONTRACTOR SHALL COORDINATE WITH THE FIELD CONDITIONS FOR THE EXACT LOCATION AND MODIFY DUCTS/PIPES ACCORDINGLY.
- 16. CONTRACTOR SHALL FIELD VERIFY AVAILABLE SPACE FOR DUCTWORK BEFORE FABRICATING. CONTRACTOR SHALL MODIFY DUCTWORK TO FIT AVAILABLE FIELD
- 17. ALL MATERIAL INSTALLED IN RETURN AIR PLENUM SHALL HAVE FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE DEVELOPED INDEX OF NOT MORE THAN 50.
- 19. INSTALL PLENUM RATED ELECTRICAL AND LOW VOLTAGE CABLE IN RETURN AIR PLENUM.
- 20. SIZE REFRIGERANT PIPING PER MANUFACTURERS RECOMMENDATIONS FOR ACTUAL LINE LENGTHS AND VERTICAL LIFT REQUIRED.
- 21. ALL EXTERIOR WALL AND ROOF PENETRATIONS SHALL BE SEALED WATERPROOF.
- 22. PROVIDE FIRESTOP WHERE PIPES, CONDUITS, BUS DUCTS, WIRES, DUCTS, AND SIMILAR BUILDING SERVICE EQUIPMENT PENETRATING RATED FLOORS AND WALLS.
- 23. ALL CEILING EQUIPMENT SHALL BE INSTALLED IN SUCH A WAY THAT LIGHTS, PIPING,
- AND DUCTWORK DO NOT BLOCK ACCESS TO UNITS AND RELATED ACCESSORIES.
- 24. ALL DUCT SIZES SHOWN ARE NET INSIDE CLEAR DIMENSIONS. 25. PROVIDE VOLUME DAMPERS AT EACH BRANCH TAKEOFF AND IN SUCH OTHER
- LOCATIONS WHERE REQUIRED TO PROPERLY BALANCE THE SYSTEM. 26. PROVIDE INSTRUMENT TEST HOLES WITH CAPS IN AIR DISTRIBUTION SYSTEMS
- WHEREVER VOLUME DAMPER ARE REQUIRED.
- 27. ALL MISCELLANEOUS STRUCTURAL SUPPORTS REQUIRED FOR HVAC EQUIPMENT INSTALLATIONS SHALL BE PROVIDED BY HVAC CONTRACTOR.
- 28. ALL TRANSFER DUCTS SHALL BE INTERNALLY LINED. 29. ALL MITERED ELBOWS SHALL BE PROVIDED WITH TURNING VANES. ALL ROUND
- ELBOWS SHALL HAVE A CENTER TO FACE DIMENSION OF 1.5 X THE DUCT WIDTH. 30. CONTRACTOR SHALL FURNISH TESTING & BALANCING REPORT TO ENGINEER & OWNER
- PRIOR TO FINAL INSPECTION TO VERIFY REQUIRED PERFORMANCE HAS ACIEVED.
- 31. ALL PIPING AND DUCTS IN FINISHED ROOMS OR SPACES SHALL BE CONCEALED IN FURRED CHASES OR SUSPENDED CEILINGS UNLESS OTHERWISE NOTED.
- 32. ACCESS PANELS IN SUSPENDED CEILINGS ARE REQUIRED FOR ALL VALVES, DAMPERS CONTROLS, ETC., AND SHALL BE FURNISHED UNDER ARCHITECTURAL SPECIFICATIONS.
- 33. DUCTWORK AND RELATED SHEET METAL WORK: A. CLASSIFICATION: LOW PRESSURE DUCTWORK SHALL BE LIMITED TO SYSTEMS
- OPERATING AT STATIC PRESSURES OF TWO INCHES OF WATER OR LESS AND HIGH PRESSURE DUCTWORK SHALL BE SYSTEMS OPERATING ABOVE TWO INCHES WATER COLUMN.

3 Specifications - Mechanical

- B. MATERIALS: MATERIALS SHALL COMPLY WITH SMACNA'S "HVAC DUCT CONSTRUCTION STANDARDS METAL AND FLEXIBLE" FOR ACCEPTABLE MATERIALS, MATERIAL THICKNESS, AND DUCT CONSTRUCTION METHODS UNLESS OTHERWISE INDICATED. SHEET METAL MATERIALS SHALL BE FREE OF PITTING, SEAM MARKS, ROLLER MARKS, STAINS, DISCOLORATIONS, AND OTHER IMPERFECTIONS. THE GALVANIZED SHEET COATING SHALL BE G60 (Z180) CONFORMING TO ASTM A 653/A 653M. HIGH PRESSURE ROUND DUCTS SHALL BE MACHINE LUBRICATED SPIRAL LOCK SEAM TYPE. ROUND FITTINGS AND ROUND SPIRAL DUCT SHALL BE AS MANUFACTURED BY SHEET METAL CONNECTORS, INC; LINDAB, INC.; SPIRAL MANUFACTURING COMPANY, INC; OR EQUAL. GASKETS FOR HIGH PRESSURE DUCTS SHALL BE 3M TYPE 1202 OR EQUAL REINFORCED SYNTHETIC RUBBER SEALANT TYPE NOT LESS THAN 1/4 INCH THICK AND 3/8" WIDE; LIQUID DUCT SEALANT SHALL BE BRUSH OR FLOW GUN GRADE WHICH REMAINS FLEXIBLE AFTER AIR CURING, 3M TYPE 800 OR EQUAL
- CONSTRUCTION: CONSTRUCT DUCTWORK (EXCEPT FLEXIBLE DUCTING) WITH CAREFUL, NEAT, AND ACCURATE WORKMANSHIP, AND AIRTIGHT JOINTS AND SEAMS. CONSTRUCT DUCTWORK AND INSTALL IN ACCORDANCE WITH LATEST EDITIONS OF SMACNA'S "LOW VELOCITY DUCT CONSTRUCTION STANDARDS" OR AS APPLICABLE TO CLASSIFICATION OF DUCTWORK INVOLVED, INCLUDING ALL APPLICABLE RECOMMENDATIONS OF THESE STANDARDS.
- 34. ALL DUCTWORK SHALL BE INSULATED EXTERNALLY WITH TWO INCH FLEXIBLE FIBERGLASS DUCT WRAP. INSULATION SHALL COMPLY WITH ANSI/ASTM C612; COMMERCIAL GRADE; 'K' VALUE OF 0.29 AT 75 °F. PROVIDE A 0.002 INCH FOIL SCRIM FACING FOR DUCTWORK INSULATION. SECURE INSULATION WITH VAPOR BARRIER WITH WIRES AND SEAL JACKET JOINTS WITH VAPOR BARRIER ADHESIVE OR TAPE TO MATCH JACKET. SECURE INSULATION WITHOUT VAPOR BARRIER WITH STAPLES, TAPE, OR WIRES. RETURN AIR DUCTS SHALL BE INSULATED
- W/ 1" ACOUSTICAL DUCT LINER, 1.5 PCF MIN. DENSITY. 36. GAS PIPING - STEEL PIPE: ASTM A 53/A 53M, BLACK STEEL, SCHEDULE 40, TYPE E OR S, GRADE B.
- A. MALLEABLE-IRON THREADED FITTINGS: ASME B16.3, CLASS 150, STANDARD PATTERN,
- B. WROUGHT-STEEL WELDING FITTINGS: ASTM A 234/A 234M FOR BUTT WELDING AND SOCKET WELDING. C. UNIONS: ASME B16.39, CLASS 150, MALLEABLE IRON WITH BRASS-TO-IRON SEAT, GROUND JOINT, AND THREADED ENDS. PIPING 3/4" TO 2" FOR SYSTEMS WITH OPERATING PRESSURE OF 2 PSIG OR LESS SHALL HAVE THREADED JOINTS. PIPING OVER 2" WITH AN OPERATING PRESSURE OF 2 PSIG OR LESS SHALL HAVE WELDED JOINTS. ALL PIPING WITH AN OPERATING PRESSURE OVER 2 PSIG SHALL BE WELDED.

plin \Box




REVISIONS

DATE OF ORIGINAL ISSUE 6/9/2024

KEYNOTES:

- CONTRACTOR TO COORDINATE WITH LOCAL UTILITY FOR NEW GAS METER AND PAY FOR ALL INCURRED
- GAS SERVICE FOR RESTURAUNT TO BE SIZED FOR 1000 CFH AT 2 PSIG. PROVIDE PRV AND SEISMIC ISOLATION VALVE AS REQUIRED. EXTEND 2" GAS UP WALL TO ROOF. PAINT ALL EXPOSED PIPING TO MATCH EXTERIOR WALL.
- METER FOR TENANT SPACE TO BE SIZED FOR 150 CFH AT 0.5 PSIG. PROVIDE PRV AND SEISMIC ISOLATION VALVE AS REQUIRED. EXTEND 1 1/4" GAS UP WALL TO ROOF. PAINT ALL EXPOSED PIPING TO MATCH EXTERIOR WALL.

FLOOR PLAN — MECHANICAL 1/8"=1'-0"



KEYNOTES:

- 1 MECHANICAL CONTRACTOR SHALL PROVIDE CURB FOR FUTURE 5 TON TRANE RTU
- (2) MECHANICAL CONTRACTOR SHALL PROVIDE CURB FOR FUTURE 7.5 TON TRANE RTU

Retail Building
7418 Hwy 70
Bartlett, TN

No.	Date	

SCALE
AS SHOWN

SHEET NUMBER

M 1 0 1

OF

DATE OF ORIGINAL ISSUE
6/9/2024

FLOOR PLAN — MECHANICAL 1/8"=1'-0"

LEGEND

 SANITARY WASTE (SW)
 SANITARY VENT (SV)
OOLD MATED (OM)

—————— COLD WATER (CW) AFF ABOVE FINISHED FLOOR


CO CLEANOUT

ELEV ELEVATION

FCO FLOOR CLEANOUT

TYP TYPICAL

PIPE DOWN	
PIPE UP	
CAP	
BALANCING VALVE	(
BALL VALVE	(
CHECK VALVE	<u> </u>



GRADE CLEANOUT DETAIL Not To Scale

_					
			PIPE SCHEDULE		
	SYSTEM	ABOVE GRADE	BELOW GRADE	JOINTS	INSULATION
	SANITARY	SCH 40 PVC	SCH 40 PVC	SOLVENT WELD	
	VENT	SCH 40 PVC	SCH 40 PVC	SOLVENT WELD	
	CW	TYPE L COPPER OR PEX	TYPE K COPPER	LEAD FREE NICKEL BEARING SOLDER	1/2" FIBERGLASS WITH ASJ
•	HW	TYPE L COPPER OR PEX	TYPE K COPPER	LEAD FREE NICKEL BEARING SOLDER	1/2" FIBERGLASS WITH ASJ
•	CONDENSATE	SCH 40 PVC, COPPER IN PLENUM RETURN	SCH 40 PVC	PVC SOLVENT WELD COPPER SOLDER	1/2" FIBERGLASS WITH ASJ

GENERAL NOTES:

1. CONTRACTOR TO FIELD VERIFY EXACT CONDITIONS PRIOR TO BEGINNING WORK.

2. CONTRACTOR SHALL COORDINATE WITH ALL DISCIPLINES INVOLVED TO AVOID ANY PIPE ROUTING PROBLEMS. IN THE EVENT CONFLICTS ARE ENCOUNTERED WHICH CANNOT BE RESOLVED BY THE TRADES INVOLVED, THE ARCHITECT SHALL BE CONSULTED AND HIS DECISION SHALL GOVERN. 3. IF ANY DISRUPTION OF SERVICES IS EXPECTED, THE CONTRACTOR SHALL CONTACT THE OWNER'S REPRESENTATIVE A MINIMUM OF 72 HOURS

AHEAD OF DISRUPTION. 4. CONTRACTOR SHALL COORDINATE EQUIPMENT CONNECTIONS WITH EQUIPMENT DRAWINGS AND SUPPLIER. CONTRACTOR SHALL INSTALL EQUIPMENT AND MAKE FINAL CONNECTIONS FURNISHING CUTOFF VALVES, P-TRAPS, PRESSURE REDUCING VALVES, AND PIPING AS REQUIRED.

5. ALL SANITARY VENT TERMINATIONS SHALL BE A MINIMUM OF 25'-0" AWAY FROM ALL FRESH AIR INTAKES FOR MECHANICAL UNITS.

6. CONTRACTOR SHALL PROVIDE INCREASERS ON SANITARY VENT PIPING PENETRATIONS THROUGH THE ROOF WHERE REQUIRED BY CODE. 7. ALL FIXTURES, EQUIPMENT AND PIPING SHOWN ON THESE DRAWINGS SHALL BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE

8. PENETRATIONS THROUGH NEW WALLS AND FLOORS SHALL BE SLEEVED AND/OR PATCHED AS DIRECTED BY THE SPECIFICATIONS. SEE ARCHITECTURAL DRAWINGS FOR FINAL FINISHES.

9. ALL NEW PIPE PENETRATIONS OF FIRE RATED WALLS, AS SHOWN BY THE LIFE SAFETY PLANS, SHALL HAVE A UL LISTED F RATING EQUAL TO THE

WALL FIRE RATING. REFER TO THE WALL PENETRATION DETAILS FOR FURTHER INFORMATION.

10. CONTRACTOR TO SEISMICALLY BRACE ALL PIPE AS REQUIRED BY LOCAL CODE REQUIREMENTS. 11. PIPING SHALL NOT BE INSTALLED OVER ELECTRICAL EQUIPMENT.

12. EXACT LOCATIONS OF MECHANICAL EQUIPMENT SHALL BE VERIFIED WITH THE MECHANICAL CONTRACTOR. ALL REQUIRED CONDENSATE PIPING

SHALL BE COORDINATED WITH THIS EQUIPMENT. 13. SANITARY SEWER PIPING SHALL BE SLOPED AS FOLLOWS: 4" SANITARY WASTE PIPING AND LARGER SHALL BE ROUTED AT 1/8" PER FOOT MINIMUM.

3" SANITARY WASTE PIPING AND SMALLER SHALL BE ROUTED AT 1/4" PER FOOT MINIMUM. 14. CONTRACTOR SHALL ESTABLISH A SEQUENCE OF INSTALLATION WITH OTHER TRADES WORKING ON THE PROJECT. CONTRACTOR SHALL

THOROUGHLY COORDINATE ALL SYSTEMS WITH OTHER TRADES.

15. CATHODIC PROTECTION, IF REQUIRED, IS THE CONTRACTOR'S RESPONSIBILITY. CONTRACTOR SHALL PROTECT ALL UNDERGROUND METALLIC PIPING FROM CORROSION. REFER TO SOILS REPORT. UNDERGROUND PIPING MAY ALSO BE PROTECTED WITH POLYETHYLENE ENCASEMENT CONFORMING TO ANSI/AWWA REQUIREMENTS. ALL PIPING SHALL BE WRAPPED COMPLETELY WITH ENCASEMENT TO A POINT AT LEAST 12 A.F.G OR FIN. FLOOR. ENCASEMENT SHALL BE FREE OF TEARS WITH ALL JOINTS COMPLETELY SEALED. NO PORTION OF THE PIPE SHALL BE LEFT EXPOSED TO

16. PROVIDE ALL REQUIRED PRV'S, VALVES, AND GUAGES AS REQUIRED BY LOCAL CODES AND PER MANUFACTURER'S REC.

17. DRAINAGE AND WATER PIPING SHALL BE TESTED PER CODE. 18. USE DIELECTRIC FITTINGS AND UNIONS ON UNSIMILAR MATERIALS.

19. BALL VALVES SHALL BE BE RATED MIN 125 PSIG AND BE FULL PORT 2 PIECE WITH SS BALL.

SPECIFICATIONS - PLUMBING


- A. MATERIALS AND WORKMANSHIP
- 1. THE PLUMBING PLANS ARE DIAGRAMMATIC AND NOT TO BE SCALED.
- 2. THE CONTRACTOR SHALL REFER TO THE ARCHITECTURAL PLANS, AND SHALL FIT THE WORK ACCURATELY TO THE
- BUILDING. B. PERMITS AND FEES
- 1. THE CONTRACTOR SHALL MAKE APPLICATION, AND PAY ALL RELATED FEES AND COSTS FOR PERMITS,
- INSPECTIONS, AND TESTS AS REQUIRED BY THE LOCAL AUTHORITY. INCLUDE COSTS IN CONTRACT PRICE. D. DRAINAGE SYSTEMS
- 1. FURNISH AND INSTALL ALL SOIL, WASTE, VENT, AND DRAIN PIPING AS INDICATED. 2. ALL ABOVE GRADE STORM DRAIN, SOIL, WASTE, VENT, AND DRAIN PIPING SHALL BE SERVICE WEIGHT NO-HUB
- CAST IRON OR DWV SCH. 40 PVC. FIXTURE PIPING EXPOSED IN FINISHED AREAS SHALL BE CHROME PLATED BRASS. FITTINGS SHALL BE DRAINAGE PATTERN AND OF THE SAME MATERIAL AS THE PIPING.
- INDIRECT WASTE AND CONDENSATE DRAIN PIPING SHALL BE DWV COPPER. ALL FITTINGS SHALL BE DRAINAGE
- PATTERN AND OF THE SAME MATERIAL AS THE PIPING. 4. SOIL, WASTE, VENT AND DRAIN PIPING SHALL BE SUBJECTED TO A WATER TEST OF NOT LESS THAN TEN FEET OF
- HYDROSTATIC HEAD FOR A PERIOD OF NOT LESS THAN THIRTY MINUTES PRIOR TO THE CONNECTION TO THE EXISTING SYSTEM.
- WATER PIPING (DOMESTIC)
- HOT, HOT RETURN, AND COLD WATER PIPING SHALL BE TYPE PEX
- FITTINGS SHALL BE PEX.
- 3. TEST WATER PIPING AT 125 PSI FOR A PERIOD OF 24 HOURS PRIOR TO THE CONNECTION TO THE EXISTING
- SYSTEM. F. PIPE JOINTS
- JOINTS IN CAST-IRON SOIL, WASTE AND VENT PIPING ABOVE GRADE SHALL BE MADE WITH NO-HUB CLAMPS.
- JOINTS IN DWV PVC PIPING SHALL BE MADE WITH SOLVENT WELD. JOINTS IN COPPER PIPING ABOVE GRADE SHALL BE SOLDERED JOINTS MADE WITH GRADE 95 TA LEAD-FREE
- SOLDER WITH A NON-CORROSIVE, PETROLEUM-BASED FLUX AS RECOMMENDED BY THE PIPE MANUFACTURER.
- 4. JOINTS IN STEEL PIPING SHALL BE THREADED AND MADE WITH STANDARD FITTINGS WITH A WORKING PRESSURE OF 165 PSI.
- JOINTS BETWEEN PIPING OF DISSIMILAR MATERIALS SHALL BE MADE USING DIELECTRIC UNIONS.
- G. BALL VALVES
- VALVES SHALL BE BRONZE OR BRASS THROUGHOUT. 2. VALVES SHALL BE RATED FOR 125 PSI, AND BE MADE BY NIBCO OR EQUAL.
- H. INSULATION
- 1. COLD WATER AND CONDENSATE DRAIN PIPING ABOVE GRADE SHALL BE COVERED WITH 1/2" FIBERGLASS INSULATION WITH ALL-SERVICE JACKET.
- 2. HOT WATER SUPPLY AND RETURN PIPING ABOVE GRADE SHALL BE COVERED WITH 1" FIBERGLASS INSULATION
- WITH ALL-SERVICE JACKET. HANGERS
- 1. HANGERS FOR COPPER PIPING SHALL BE CLEVIS OR SPLIT-RING AS MANUFACTURED BY GRINNELL OR EQUAL, AND SHALL BE COPPER-CLAD OR PVC-COATED TO PREVENT GALVANIC CORROSION.
- 2. HANGERS FOR SOIL, WASTE, VENT AND DRAIN PIPING SHALL BE CLEVIS HANGERS AS MANUFACTURED BY GRINNELL OR EQUAL.
- J. CLEAN-UP
- 1. AFTER ALL FIXTURES HAVE BEEN SET, INSPECTED, AND TESTED THEY SHALL BE THOROUGHLY CLEANED BY THE PLUMBING CONTRACTOR PRIOR TO LEAVING THE SITE.

nild \Box tail Re




REVISIONS Date

SHEET NUMBER DATE OF ORIGINAL ISSUE 6/9/2024



REFER TO CIVIL PLANS FOR CONTINUATION OF 4" SW MAIN.



- PROVIDE NEW METERED 1 ½" CW FOR FUTURE TENANT. EXTEND CW THRU FLOOR WITH CAP AND BALL VALVE. EXTEND MAIN TO STREET WITH METER. SEE CIVIL
- ROUTE 1 1/2" CW MAIN THRU FLOOR AND BELOW GRADE. EXTEND MAIN TO EXISTING SITE MAIN AS REQUIRED. COORDINATE WITH LOCAL UTILTITY & PROVIDE TAP AND METER AS REQUIRED CONTRACTOR TO PAY FOR ALL INCURRED COST

THESE DRAWINGS AND SPECIFICATIONS ARE OWNED AND COPYRIGHTED BY <u>GUY PAYNE & ASSOCIATES ARCHITECT P.C.</u> AND MAY NOT BE USED, COPIED, OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT. ANY UNAUTHORIZED OR DISCLOSURE OF THE PROPRIETARY INFORMATION CONTAINED HEREIN MAY SUBJECT SUCH PERSONS TO CRIMINAL AND CIVIL PENALTIES AND DAMAGES.


& ASSOCIATES ARCHITEC WILLOW CIRCLE, STE. 114

JUY PAYNE & ASSOCIATES
879 WILLOW CIRCLE, STE
CORDOVA, TENNESSEE 38

Retail Building
7418 Hwy 70
Bartlett, TN




REVISIO	ONS
No.	Date
	PROJECT NUMBER



CALLOUT	SYMBOL	DESCRIPTION	MOUNTING	MODEL	INPUT WATTS	VOLTS	NOTE 1
В	0	6" LED WET LOCATION DOWNLIGHT	RECESSED	LITHONIA LDN6 15LM 35K LO6 WR TRW LSS WD MVOLT	20.5	120V 1P 2W	
BE	•	6" LED WET LOCATION DOWNLIGHT	RECESSED	LITHONIA LDN6 15LM 35K LO6 WR TRW LSS WD MVOLT ELR	20.5	120V 1P 2W	BATTERY BACKUP
С	0	4' LED STRIPLIGHT	CHAIN HUNG	METALUX # SNLED-LD5-54SL-LW-UNV-L840-CD1-U	36	120V 1P 2W	
E	⊦⊗	EXIT SIGN COMBO	WALL/CEILING	DUAL LITE #EVC-U-R-W	5	120V 1P 2W	CONNECT TO UNSWITCHED "LIFE SAFETY" CIRCUIT
EG	۵	OUTDOOR EMERGENCY LIGHT	WALL	DUAL-LITE, PGN Series	17.7	120V 1P 2W	CONNECT UNSWITCHED HOT FROM CIRCUIT DIRECTLY INDOOR FROM FIXTURE PROVIDE "SWITCHED" HOT FROM PHOTOCELL CIRCUIT AS INDICATED
EL	[k	EMERGENCY EGRESS LIGHTS	WALL	LITHONIA ELM6L	5	120V 1P 2W	PROVIDE FULLY RECESSED KIT ELA FRK
S01	○ —□	RSX Area Fixture Size 1 P2 Lumen Package 4000K CCT Type R4 Distribution with EGS Shield	POLE	Lithonia Lighting, RSX1 LED P2 40K R4 EGS PROVID 20' SQUARE STEEL POLE,FINISH TO MATCH FIXTURE	72.9467	208V 2P 2W	,PROVIDE 20 FOOT POLE
W1	早	WPX1 LED wallpack 3000lm 4000K color temperature 120-277 Volts	WALL, MTD PER ARCH	Lithonia Lighting, WPX1 LED P2 40K Mvolt GLASS BLOCK	24.42	120V 1P 2W	COORDINATE HEIGHT WITH ARCHITCET
W3	⊦⊗	OUTDOOR LED WALL CYLINDER UP/DOWN LIGHT	WALL, MTD PER ARCH	SELECTED BY OWNER	9.02	120V 1P 2W	DECORATIVE SCONCE OWNER APPROVED

SWITCH SCH	EDULE		
CALLOUT	SYMBOL	NOTE 1	NOTE 2
THREEWAY SWITCH	\$ 3	WALL MOUNTED 3 WAY SWITCH MTD 48" AFF. UOI.	

H)													
ROOM MOUN FED F	NTING FI	LUSH ITILITY		E	VOLTS BUS AMP NEUTRAL		V 3P 4W			AIC 22,000 MAIN BKR LUGS STAN	100 DARD			
СКТ	CKT				I	_OAD KV	4	СКТ	CKT			L	OAD KV	Ą
#	BKR	CIRCUIT D	ESCRIPTION		Α	В	С	#	BKR	CIRCUIT DESCRIPTION	N	Α	В	С
1	20/1	LIGHTING			0.195			2	20/1	SPACE		0		
3	20/1	LIGHTING				0.072		4	20/1	SPACE		•	0	
5	20/2	LIGHTING				İ	0.255	6	20/2	SPACE				0
7					0.255	İ		8				0		
9	20/1	LIGHTING				0.246		10	20/1	SPACE			0	
11	20/1	SPACE					0	12	20/1	SPACE				0
13	20/1	SPACE			0			14	20/1	SPACE		0		
15	20/1	SPACE				0		16	20/1	SPACE			0	
17	20/2	SPACE			1		0	18	20/1	SPACE				0
19					0					TOTAL CONNECTED KV	'A BY PHASE	0.451	0.318	0.255
			CONN KVA	CALC KVA							CALC KVA	1	1	'
LIGHTING 1.02 1.28		1.28	 (12	25%)		TOT	AL LOA	D	1.28	_				
								BAL	ANCED	3-PHASE LOAD	3.55 A			



ELECTRICAL SYMBOLS

- ☐ NONFUSED DISCONNECT SWITCH SIZE AS INDICATED
- √ FUSED DISCONNECT SWITCH SIZE AS INDICATED
- COMBINATION STARTER/DISCONNECT SIZE AS INDICATED
- \$ TOGGLE SWITCH


FEEDER/BRANCH RUN OVERHEAD - CONCEALED IN OR ABOVE CEILING, IN WALL, OR EXPOSED ON STRUCTURE MC — — — — EMERGENCY, NIGHT LIGHT, OR FEEDER/BRANCH CONCEALED BELOW FLOOR, IN WALL, OR BELOW

HOME RUN TO CIRCUIT PANEL, NEUTRAL/HOT/GROUND. #12 COPPER, UOI


ABBREVIATIONS

a,b,c, etc. DENOTES SWITCHING SCHEME MOUNT ABOVE COUNTER AFF ABOVE FINISHED FLOOR ABOVE FINISHED GRADE BELOW FINISHED GRADE ELECTRICAL CONTRACTOR EP EXPLOSION PROOF EX **EXISTING** FAA FIRE ALARM ANNUNCIATOR PANEL FACP FIRE ALARM CONTROL PANEL GENERAL CONTRACTOR GROUND FAULT CIRCUIT INTERRUPTER MECHANICAL CONTRACTOR MOUNTED OFCI OWNER FURNISHED, CONTRACTOR INSTALLED SPD SURGE PROTECTIVE DEVICE STB

SHUNT TRIP BREAKER UNLESS OTHERWISE INDICATED WEATHERPROOF



UOI



Seismic Mounting Detail
no scale


Retail Building
7418 Hwy 70
Bartlett, TN



-	
REVISION	ONS
No.	Date

SCHEDULES -ELECTRICAL

SHEET NUMBER DATE OF ORIGINAL ISSUE 6/9/2024



SERVICE ENTRY NOTES:


1. UNDERGROUND SERVICE LATERAL CONDUCTORS MUST BE PROTECTED FROM DAMAGE IN ACCORDANCE WITH ARTICLE 300.5. UNDERGROUND SERVICE CONDUCTORS THAT ARE NOT ENCASED IN CONCRETE AND THAT ARE BURIED 18" OR MORE BELOW GRADE SHALL HAVE THEIR LOCATION IDENTIFIED BY A WARNING RIBBON PLACED 12" ABOVE THE UNDERGROUND INSTALLATION.

UTILITY METERS

- 2. UNLESS LOCAL CODE DICTATES OTHERWISE, PVC SERVICE ENTRANCE LATERAL RACEWAY MUST BE BURIED AT LEAST 18" TO TOP OF THE RACEWAY UNLESS BELOW A COVERING OF AT LEAST 2" OF CONCRETE. RACEWAY COVERED UNDER 2" OF CONCRETE MUST BE BURIED AT LEAST 12" TO TOP OF RACEWAY.
- 3. BACKFILL THAT CONTAINS LARGE ROCKS, PAVING MATERIALS, CORROSIVE MATERIAL OR ANYTHING ELSE THAT MAY CAUSE DAMAGE TO RACEWAYS OR CABLES IS NOT PERMITTED.
- 4. CONDUITS OR RACEWAYS THROUGH WHICH MOISTURE MAY CONTACT LIVE PARTS SHALL BE SEALED OR PLUGGED AT ONE OR BOTH ENDS. SPARE OR UNUSED RACEWAYS SHALL ALSO BE SEALED. SEALANTS SHALL BE IDENTIFIED FOR USE WITH THE CABLE, INSULATION, SHIELD OR OTHER COMPONENTS.
- 5. PARALLEL SERVICE CONDUCTORS MUST BE THE SAME LENGTH, HAVE THE SAME CONDUCTOR MATERIAL, BE THE SAME SIZE, HAVE THE SAME INSULATION TYPE, AND BE TERMINATED IN THE SAME MANNER. IN ADDITION THE RACEWAYS OR CABLES MUST HAVE THE SAME PHYSICAL CHARACTERISTICS.

ONE LINE NOTES

- IN ACCORDANCE WITH NEC ARTICLE 110.16. ELECTRICAL EQUIPMENT LIKELY TO REQUIRE EXAMINATION WHILE ENERGIZED SHALL BE FIELD MARKED TO WARN PERSONNEL OF POTENTIAL ARC FLASH HAZARDS. THIS SHALL BE FURNISHED FROM THE FACTORY.
- IN ACCORDANCE WITH NEC ARTICLE 110.24. THE SERVICE EQUIPMENT SHALL BE FIELD MARKED WITH THE MAXIMUM AVAILABLE FAULT CURRENT ALONG WITH THE DATE THE CALCULATION WAS PERFORMED.
- 3. ALL WORKING SPACE REQUIREMENTS AROUND ELECTRICAL EQUIPMENT IN ACCORDANCE WITH NEC SHALL BE STRICTLY ADHERED TO BY ALL TRADES.
- 4. CONTRACTOR SHALL BE RESPONSIBLE TO USE THE INFORMATION PROVIDED IN THE SHORT CIRCUIT AND COORDINATION STUDY TO VERIFY THAT SETTINGS ON ADJUSTABLE TRIP OVERCURRENT DEVICES MATCH THE RECOMMENDATIONS OF THE SHORT CIRCUIT AND COORDINATION STUDY.
- 5. IN ACCORDANCE WITH NEC 230.8 RACEWAYS ENTERING A BUILDING FROM AN UNDERGROUND DISTRIBUTION SYSTEM SHALL BE SEALED IN ACCORDANCE WITH 300.5.G.
- 6. ALL PANELS SHALL HAVE COPPER BUSSING.
- ALL PANELBOARDS SHALL BE RATED FOR BASED ON SEISMIC CATEGORY. SEE STRUCTURAL PLANS FOR CATEGORY DETAILS.
- 8. CONTRACTOR SHALL PROVIDE SPARE BREAKERS AS INDICATED ON PANEL SCHEDULES.
- 9. REFER TO MAIN GROUNDING BUS DETAIL FOR MAIN GROUNDING DIAGRAM.
- 10. ALL PANELBOARDS TO BE EASY TRIM TYPE.



COPTRIGHTED BY GUT PATNE & ASSOCIATES ARCHITECTS.

P.C. AND MAY NOT BE USED, COPIED, OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT. ANY UNAUTHORIZED UOR DISCLOSURE OF THE PROPRIETARY INFORMATION CONTAINED HEREIN MAY SUBJECT SUCH PERSONS TO

E & ASSOCIATES ARCHI'79 WILLOW CIRCLE, STE. 114
CORDOVA, TENNESSEE 38018

Retail Building



_			i
	REVISIO	ONS	
	No.	Date	

ONE LINE -ELECTRICAL

SCALE
AS SHOWN

SHEET NUMBER

E002

OF

DATE OF ORIGINAL ISSUE

6/9/2024

PROJECT NUMBER

A														
ROO	M			V	OLTS :	208Y/120	V 3P 4W			AIC 22,000				
IUON	NTING F	LUSH		Е	BUS AMPS 400					MAIN BKR 4	.00			
ED F	ROM L	JTILITY		N	NEUTRAL	100%				LUGS STANE	DARD			
NOTE	<u> </u>													
CKT	CKT				L	OAD KV	Α	СКТ	CKT			L	OAD KV	Ą
#	BKR	CIRCUIT	DESCRIPTION		Α	В	С	#	BKR	CIRCUIT DESCRIPTION		Α	В	С
1	20/1	LIGHTING	i		0.326			2	20/1	SPACE		0		
3	20/1	SPACE		İ		0		4	20/1	SPACE			0	
5	20/1	SPACE					0	6	20/1	SPACE				0
7	20/1	SPACE			0			8	20/1	SPACE		0		
9	20/1	SPACE				0		10	20/1	SPACE			0	·
11	20/1	SPACE					0	12	20/1	SPACE				0
13	20/1	SPACE			0			14	20/1	SPACE		0		
15	20/1	SPACE				0	İ	16	20/1	SPACE			0	
17	20/1	SPACE					0	18	20/1	SPACE				0
19	20/1	SPACE			0			20	20/1	SPACE		0		
21	20/1	SPACE				0		22	20/1	SPACE			0	
23	20/1	SPACE					0	24	20/1	SPACE				0
25	20/1	SPACE			0		İ	26	20/1	SPACE		0		
27	20/1	SPACE				0		28	20/1	SPACE			0	
29	20/1	SPACE					0	30	20/1	SPACE				0
31	20/1	SPACE			0			32	20/1	SPACE		0		
33	20/1	SPACE				0		34	20/1	SPACE			0	
35	20/1	SPACE					0	36	20/1	SPACE				0
37	20/1	SPACE			0			38	20/1	SPACE		0		
39	20/1	SPACE				0		40	20/1	SPACE			0	
41	20/1	SPACE					0	42	20/1	SPACE				0
										TOTAL CONNECTED KVA	A BY PHASE	0.326	0	0
			CONN KVA	CALC KVA			I	1			CALC KVA			I
LIC	SHTING		0.326	0.407	— (12	25%)			AL LOA	D 3-PHASE LOAD	0.407 1.13 A	_		

ROOM MOUNTING FLUSH FED FROM UTILITY NOTE		Е	VOLTS 208Y/120V 3P 4W BUS AMPS 200 NEUTRAL 100%					AIC 22,000 MAIN BKR 200 LUGS STANDARD					
СКТ	CKT				L	OAD KVA	4	CKT	CKT		L	OAD KV	4
#	BKR	CIRCUIT	DESCRIPTION		Α	В	C	#	BKR	CIRCUIT DESCRIPTION	Α	В	
1	20/1	LIGHTING			0.326			2	20/1	SPACE	0		
3	20/1	SPACE				0		4	20/1	SPACE		0	•
5	20/1	SPACE			ļ		0	6	20/1	SPACE			(
7	20/1	SPACE			0			8	20/1	SPACE	0		İ
9	20/1	SPACE			ļ	0		10	20/1	SPACE		0	İ
11	20/1	SPACE					0	12	20/1	SPACE			(
13	20/1	SPACE			0		·	14	20/1	SPACE	0		
15	20/1	SPACE				0		16	20/1	SPACE		0	
17	20/1	SPACE					0	18	20/1	SPACE			(
19	20/1	SPACE			0			20	20/1	SPACE	0		İ
21	20/1	SPACE				0		22	20/1	SPACE		0	
23	20/1	SPACE			İ		0	24	20/1	SPACE			(
25	20/1	SPACE			0			26	20/1	SPACE	0		
27	20/1	SPACE			İ	0		28	20/1	SPACE		0	
29	20/1	SPACE			İ		0	30	20/1	SPACE			(
31	20/1	SPACE			0			32	20/1	SPACE	0		
33	20/1	SPACE			İ	0		34	20/1	SPACE		0	
35	20/1	SPACE			İ		0	36	20/1	SPACE			(
37	20/1	SPACE			0			38	20/1	SPACE	0		
39	20/1	SPACE			ļ	0		40	20/1	SPACE		0	
41	20/1	SPACE			ļ		0	42	20/1	SPACE			(
		•								TOTAL CONNECTED KVA BY PHAS	SE 0.326	0	(
			CONN KVA	CALC KVA						CAL KVA			
LIG	HTING		0.326	0.407	— (12	25%)		TOT	AL LOA	D 0.407			
			-	-	` -	,				3-PHASE LOAD 1.13 A			

	NTING F	LUSH ITILITY		В	OLTS 2 US AMPS EUTRAL		V 3P 4W			AIC 22,000 MAIN BKR 200 LUGS STANDARD			
СКТ				LOAD KVA			СКТ	CKT CKT		L	LOAD KVA		
#	BKR	CIRCUIT	ESCRIPTION		Α	В	С	#	BKR	CIRCUIT DESCRIPTION	Α	В	С
1	20/1	LIGHTING			0.326			2	20/1	SPACE	0		
3	20/1	SPACE			İ	0		4	20/1	SPACE		0	
5	20/1	SPACE			İ		0	6	20/1	SPACE			0
7	20/1	SPACE			0			8	20/1	SPACE	0		
9	20/1	SPACE			İ	0		10	20/1	SPACE		0	
11	20/1	SPACE			İ		0	12	20/1	SPACE			0
13	20/1	SPACE			0			14	20/1	SPACE	0		
15	20/1	SPACE			İ	0		16	20/1	SPACE		0	
17	20/1	SPACE			İ		0	18	20/1	SPACE			0
19	20/1	SPACE			0			20	20/1	SPACE	0		
21	20/1	SPACE			İ	0		22	20/1	SPACE		0	
23	20/1	SPACE			İ		0	24	20/1	SPACE			0
25	20/1	SPACE			0			26	20/1	SPACE	0		
27	20/1	SPACE			İ	0		28	20/1	SPACE		0	
29	20/1	SPACE					0	30	20/1	SPACE	1		0
31	20/1	SPACE			0			32	20/1	SPACE	0		
33	20/1	SPACE				0		34	20/1	SPACE	1	0	
35	20/1	SPACE			İ		0	36	20/1	SPACE			0
37	20/1	SPACE			0			38	20/1	SPACE	0		
39	20/1	SPACE			į	0		40	20/1	SPACE		0	
41	20/1	SPACE					0	42	20/1	SPACE			0
										TOTAL CONNECTED KVA BY PHASE	0.326	0	0
			CONN KVA	CALC KVA	1			•		CALC KVA			•
LIC	HTING		0.326	0.407	_ (12	5%)		TOT	AL LOA	.D 0.407			
~			3.323	J J.	(- / - /				3-PHASE LOAD 1.13 A			

ROOM MOUNTING FLUSH FED FROM UTILITY NOTE		Е	VOLTS 208Y/120V 3P 4W BUS AMPS 400 NEUTRAL 100%					AIC 22,000 MAIN BKR 400 LUGS STANDARD						
СКТ	CKT				L	OAD KVA	4	СКТ	кт скт			LOAD KVA		
#	BKR	CIRCUIT	DESCRIPTION	Ī	Α	В	С	#	BKR	CIRCUIT DESCRIPTION	-	Α	В	С
1	20/1	LIGHTING	 }		0.326			2	20/1	SPACE		0		
3	20/1	SPACE				0		4	20/1	SPACE			0	
5	20/1	SPACE					0	6	20/1	SPACE				0
7	20/1	SPACE			0			8	20/1	SPACE		0		
9	20/1	SPACE				0		10	20/1	SPACE			0	
11	20/1	SPACE		İ			0	12	20/1	SPACE				0
13	20/1	SPACE		İ	0			14	20/1	SPACE		0		
15	20/1	SPACE		İ		0		16	20/1	SPACE			0	
17	20/1	SPACE		İ			0	18	20/1	SPACE				0
19	20/1	SPACE		İ	0			20	20/1	SPACE		0		
21	20/1	SPACE		İ		0		22	20/1	SPACE			0	
23	20/1	SPACE		İ			0	24	20/1	SPACE				0
25	20/1	SPACE		İ	0			26	20/1	SPACE		0		
27	20/1	SPACE		İ		0		28	20/1	SPACE			0	
29	20/1	SPACE		İ			0	30	20/1	SPACE				0
31	20/1	SPACE		İ	0			32	20/1	SPACE		0		
33	20/1	SPACE		İ		0		34	20/1	SPACE			0	
35	20/1	SPACE		İ			0	36	20/1	SPACE				0
37	20/1	SPACE		İ	0			38	20/1	SPACE		0		
39	20/1	SPACE		İ		0		40	20/1	SPACE		l	0	
41	20/1	SPACE					0	42	20/1	SPACE				0
										TOTAL CONNECTED KVA	BY PHASE	0.326	0	0
			CONN KVA	CALC KVA							CALC KVA			
l IC	HTING		0.326	0.407	— (12	25%)		TOT	AL LOA	.D	0.407	_		

COPYRIGHTED BY GUY PAYNE & ASSOCIATES ARCHITEC P.C. AND MAY NOT BE USED, COPIED, OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT. ANY UNAUTHORIZED OR DISCLOSURE OF THE PROPRIETARY INFORMATION CONTAINED HEREIN MAY SUBJECT SUCH PERSONS TO CRIMINAL AND CIVIL PENALTIES AND DAMAGES.

TUY PAYNE & ASSOCIATES ARCHI 879 WILLOW CIRCLE, STE. 114

Retail Building
7418 Hwy 70
Bartlett, TN



	-
REVISIO	ONS
No.	Date

PANELBOARD & EQUIPMENT SCHEDULES - ELECTRICAL

PROJECT NUMBER
4202
SCALE
AS SHOUN
SHEET NUMBER

EOO3

OF
DATE OF ORIGINAL ISSUE
6/9/2024

GENERAL NOTES

- 1. ALL ELECTRICAL WORK AND MATERIALS SHALL COMPLY WITH THE NEC (NATIONAL ELECTRICAL CODE) AND THE REQUIREMENTS OF ANY STATE AND LOCAL AUTHORITIES HAVING JURISDICTION.
- SEE PANEL SCHEDULES FOR ADDITIONAL CIRCUIT, CONDUIT AND LOAD INFORMATION
- WHERE EXPOSED AND SUBJECT TO DAMAGE, CONDUIT SHALL BE GRC UP
- TO 10' AFF. 4. MINIMUM CONDUIT SIZE SHALL BE 3/4" AND MINIMUM WIRING SIZE SHALL BE
- #12AWG ALL CIRCUIT WIRING SHALL BE THHN TYPE WIRING. CIRCUIT WIRING IN
- FREEZER/COOLER AREAS SHALL BE XHHW TYPE INSULATION WIRING. MULTIPLE CIRCUITS MAY BE COMBINED INTO A SINGLE CONDUIT ONLY BY APPLYING NEC ARTICLE 310.15.B.2. CONDUCTOR SIZES LISTED ON THE
- PANEL SCHEDULES DO NOT ACCOUNT FOR THE COMBINING OF CIRCUITS 7. LOCATE RECEPTACLES IN THE WEB OF COLUMNS WHERE POSSIBLE OR AS
- INDICATED ON THE DRAWINGS. COORDINATE WITH OTHER TRADES. 8. SLIGHT MODIFICATIONS TO DESIGNED CIRCUITRY ARE PERMITTED PROVIDED CIRCUIT LOADING, DERATING, BALANCE, AND VOLTAGE DROP ARE TAKEN INTO CONSIDERATION. ALL MODIFICATIONS MUST BE
- DILIGENTLY NOTED ON THE "AS-BUILT" DRAWING SET. 9. ALL BRANCH CIRCUIT SHALL BE INSTALLED USING EMT CONDUIT WITH COMPRESSION FITTINGS. IN ENGINEER/ARCHITECT APPROVED AREAS, MC CABLE SHALL BE PERMITTED, UOI.
- 10. MC CABLE SHALL BE SUPPORTED AND SECURED AT INTERVALS NOT EXCEEDING 6' AND WITHIN 12" OF EVERY BOX, CABINET, FITTING OR OTHER CABLE TERMINATION UNLESS OTHERWISE PERMITTED BY NEC. SEE ARTICLE 330 FOR FURTHER INFORMATION.
- 11. EMT SHALL BE SECURELY FASTENED IN PLACE AT LEAST EVERY 10'. IN ADDITION, EACH EMT RUN SHALL BE SECURELY FASTENED WITHIN 3' OF EACH OUTLET BOX, JUNCTION BOX, DEVICE BOX, CABINET, CONDUIT BODY. SEE ARTICLE 358 FOR FURTHER INFORMATION.
- 12. DO NOT SUPPORT RACEWAYS, BOXES, CABINETS, FITTINGS, CABLE ASSEMBLIES OR FIXTURES TO THE CEILING GRID SUPPORT SYSTEM. INDEPENDENT SUPPORT WIRES MAY BE USED AS A SOLE MEANS OF SUPPORT PROVIDED THEY ARE SECURED AT BOTH ENDS AND DISTINGUISHABLE BY COLOR, TAGGING OR OTHER EFFECTIVE MEANS FOR THE CEILING GRID SUPPORT SYSTEM.
- 13. ALL 208/120 VOLT WIRING SHALL ADHERE TO A "BLACK-RED-BLUE" COLOR
- 14. AT LEAST 6" OF FREE CONDUCTOR, SHALL BE LEFT AT EACH OUTLET, JUNCTION, AND SWITCH POINT FOR SPLICES OR THE CONNECTION OF FIXTURES OR DEVICES WITH THE EXCEPTION OF CONDUCTORS THAT ARE NOT SPLICED OR TERMINATED AT THE OUTLET. JUNCTION. OR SWITCH
- 15. ALL CIRCUIT DESIGNATIONS SHALL BE MARKED ON JUNCTION BOXES WHERE THEY SPLICE OR PASS THROUGH.
- 16. ALL CEILING MOUNTED 4" SQUARE JUNCTION BOXES SHALL BE 2 1/8" DEEP.
- DEVICE BOXES (4" SQUARE AND PLASTER RING) MAY BE 1-1/2" DEEP. 17. THE NUMBER OF CONDUCTORS IN A JUNCTION BOX SHALL BE SUBJECT TO
- 18. IN WALLS OR CEILINGS WITH A SURFACE OF CONCRETE, TILE, GYPSUM, PLASTER, OR OTHER NONCOMBUSTIBLE MATERIAL, BOXES SHALL BE INSTALLED SO THAT THE FRONT EDGE OF THE BOX (OR PLASTER RING) WILL NOT BE SET BACK OF THE FINISHED SURFACE MORE THAN 1/4". (NEC 314.20).
- 19. BOXES SHALL BE INSTALLED SO THE WIRING CONTAINED WITHIN IS **ACCESSIBLE**

THE PROVISIONS OF NEC ARTICLE 314.16

- 20. METAL BOXES SHALL BE GROUNDED BY AN APPROVED MEANS. 21. WHERE NAILS OR SCREWS ARE LIKELY TO PENETRATE EMT OR MC CABLE, A STEEL SLEEVE, STEEL PLATE, OR STEEL CLIP NOT LESS THAN 1/16"
- THICKNESS SHALL BE USED TO PROTECT THE CABLE OR TUBING. 22. MOUNTING HEIGHTS OF WALL OUTLETS AFF TO BOTTOM SHALL BE AS FOLLOWS, UOI ON PLANS: SWITCHES-48", RECEPTACLES & PHONE/DATA OUTLETS IN OFFICE AREAS-18".
- 23. WHERE DEVICES ARE SHOWN TO BE INSTALLED ABOVE CASEWORK OR COUNTERS, EXACT LOCATION OF DEVICES SHALL BE COORDINATED WITH THE CASEWORK CONTRACTOR BEFORE ROUGH-IN WORK IS COMPLETED.
- 24. WHERE A GFCI RECEPTACLE IS USED, THE RECEPTACLE SHALL NOT BE LOCATED TO CONCEAL THE RECEPTACLE. IT MUST BE READILY ACCESSIBLE. PROVIDE GFCI BREAKER IF RECEPTACLE AS ALTERNATIVE PROTECTION.

GENERAL NOTES (CONT)

- 1. ALL FIRE BARRIER PENETRATIONS SHALL BE MADE WITH U.L. LISTED **ASSEMBLIES**
- 2. ALL MAJOR FEEDERS SHALL BE INSTALLED UNDER SLAB/UNDERGROUND
- USING SCHEDULE 40 PVC WHERE ACCEPTABLE. 3. ALL UNDERGROUND CONDUIT RUNS ENTERING THE BUILDING SHALL BE
- SEALED TO PREVENT THE ENTRANCE OF MOISTURE AND GASES. 4. PROVIDE PROPER CONDUIT SEAL OFF AND INSULATION AT WALL
- PENETRATIONS BETWEEN AREAS OF DIFFERENT TEMPERATURES THE METHOD OF INSTALLING CONDUIT THROUGH INSULATED WALL SHALL **BE AS FOLLOWS**
- 5.1. HOLE SHALL BE CUT NEAT AT 1/4" LARGER THAN CONDUIT. CONDUIT SHALL BE OF A PVC TYPE WHICH WILL EXTEND BEYOND WALL
- FOR 1" ON EACH FACE. 5.3. AFTER WIRE HAS BEEN INSTALLED, CONDUIT SHALL BE FILLED SOLID
- WITH DUCT SEAL PLASTIC FILLER. 5.4. AFTER ALL WIRING IS COMPLETED, INSULATION CONTRACTOR SHALL SEAL CONDUIT WITH URETHANE FOAM AND VAPOR SEAL AROUND
- OUTSIDE OF CONDUIT. 6. ALL EMERGENCY CIRCUIT BOXES AND ENCLOSURES (INCLUDING TRANSFER SWITCHES, GENERATORS, AND POWER PANELS) FOR EMERGENCY CIRCUITS SHALL BE PERMANENTLY MARKED SO THEY WILL BE READILY IDENTIFIED AS A COMPONENT OF AN EMERGENCY CIRCUIT OR

SYSTEM.

- 7. EMERGENCY CIRCUIT WIRING CONSISTING OF TWO OR MORE EMERGENCY CIRCUITS SUPPLIED FROM THE SAME SOURCE SHALL BE PERMITTED IN THE SAME RACEWAY, CABLE, BOX, OR CABINET. EMERGENCY CIRCUIT WIRING SHALL BE KEPT ENTIRELY INDEPENDENT OF ALL OTHER WIRING AND EQUIPMENT OTHER THAN IN TRANSFER EQUIPMENT ENCLOSURES, EXIT OR EMERGENCY FIXTURES, COMMON JUNCTION BOX, ATTACHED TO EXIT OR EMERGENCY FIXTURES OR A COMMON JUNCTION BOX ATTACHED TO UNIT EQUIPMENT, CONTAINING ONLY THE BRANCH CIRCUIT SUPPLYING THE UNIT EQUIPMENT AND THE EMERGENCY CIRCUIT SUPPLIED BY THE UNIT **EQUIPMENT**
- REFER TO ARTICLE 300.22 FOR WIRING IN AIR HANDLING (PLENUM) SPACES. 9. ALL SPLICES SHALL BE MADE UP TIGHT USING APPROVED MATERIALS AND "PULL TESTED" FOR INTEGRITY.
- 10. FLEXIBLE CORDS/CABLES SHALL BE CONNECTED TO DEVICES AND/OR FITTINGS SO THAT TENSION IS NOT TRANSMITTED TO JOINTS OR
- 11. AN ENCLOSURE MOUNTED TO STRUCTURAL OR SUPPORTING ELEMENTS OF A SUSPENDED CEILING SHALL BE NOT MORE THAN 100 CUBIC INCHES IN SIZE AND SHALL BE SECURELY FASTENED TO THE CEILING GRID BY AN
- 12. RACEWAY CONNECTIONS TO TRANSFORMERS OR OTHER VIBRATING EQUIPMENT SHALL BE MADE USING AN APPROVED FLEXIBLE CONNECTION.
- 13. CONTRACTOR SHALL PROVIDE PUSHBUTTON FOR LOWERING CONTROL OF PROJECTOR LIFT AND MOTORIZED SCREEN. CONTRACTOR SHALL PROVIDE ALL ACCESSORIES AS REQUIRED FOR THIS OPERATION, COORDINATE WITH A/V VENDORS.
- 14. CONTRACTOR SHALL PROVIDE ALL CONNECTIONS AS REQUIRED FOR ALL KITCHEN EQUIPMENT. CONTRACTOR SHALL COORDINATE EXACT
- REQUIREMENTS PRIOR TO ROUGH-IN. REFER TO KITCHEN PLANS. 15. ALL RECEPTACLES IN KITCHEN/RESTROOM AREAS SHALL HAVE GFCI
- PROTECTION (GFCI BREAKER OR GFCI RECEPTACLE). 16. WHEREVER MODULAR FURNITURE MAY BE USED, COORDINATE THE LOCATION OF RECEPTACLES WITH OPENINGS IN THE FURNITURE. THIS IS
- CRITICAL TO PREVENT REWORK. 17. PLAN LAYOUT SHOWN IN THESE DOCUMENTS ARE SCHEMATIC AND ARE INTENDED TO ILLUSTRATE DESIGN INTENT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FINAL DESIGN INCLUDING BUT NOT LIMITED TO SERVICE
- ENTRY, PANEL SIZE, AND CIRCUITRY. 18. THE SCOPE OF WORK INDICATED SHALL BE EXECUTED IN ACCORDANCE WITH ALL APPLICABLE CODES INCLUDING, BUT NOT LIMITED TO, THE
- STANDARD ELECTRIC CODE AND THE NEC (LATEST APPLICABLE EDITION). 19. THE ELECTRICAL WORK SHOWN ON THE SUBMITTED PLANS SHALL BE PERFORMED BY A LICENSED ELECTRICAL CONTRACTOR. THE CONTRACTOR SHALL SECURE AN ELECTRICAL PERMIT FOR THEIR PORTION OF THE WORK
- PRIOR TO INSTALLATION. 20. COORDINATE ALL ELECTRICAL WORK WITH OTHER TRADES. 21. CONFIRM ELECTRICAL REQUIREMENTS FOR ANY OWNER SUPPLIED ITEMS
- PRIOR TO WIRING OR FINAL CIRCUITING.
- 22. SUBMIT CUT SHEETS FOR ELECTRICAL FIXTURES TO OWNER/ARCHITECT. 23. OUTLETS OF ANY TYPE SHALL NEVER BE INSTALLED BACK TO BACK.
- OUTLETS IN RATED WALL MUST BE INSTALLED 24" APART. 24. ALL LOW VOLTAGE WIRING, WITH EXCEPTION OF THE FIRE ALARM SYSTEM,
- IS THE OWNER'S RESPONSIBILITY. 25. CONTRACTOR SHALL PROVIDE J-HOOKS ON 24" SPACING ABOVE CEILING
- AS REQUIRED FOR NEW DATA CABLING. COORDINATE WITH OWNER. 26. IF REQUIRED, CONTRACTOR SHALL PROVIDE ALL ACCESSORIES FOR
- PROPER OPERATION OF ELECTRONIC LOCKING DOORS. DOOR LOCKS SHALL RELEASE UPON FIRE ALARM ACTIVATION. PROVIDE RELAYS FROM DOOR CONTROLLER TO FIRE ALARM CONTROL PANEL AS REQUIRED. COORDINATE ALL WORK WITH VENDOR.

GENERAL EQUIPMENT NOTES

THERMOSTATS, CONTROL WIRING, DUCT DETECTORS, ETC.

- CONTRACTOR SHALL PROVIDE ALL POWER CONNECTIONS AS REQUIRED FOR ALL MECHANICAL AND PLUMBING EQUIPMENT. COORDINATE EXACT REQUIREMENTS PRIOR TO ROUGH-IN.
- CONTRACTOR SHALL PROVIDE 120V CIRCUITS FOR ALL MECHANICAL CONTROL PANELS AS REQUIRED. COORDINATE WITH MC.
- 3. PROPER CLEARANCE MUST BE MAINTAINED AROUND ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.26.
- PANELBOARDS, STARTERS, DISCONNECT SWITCHES, ETC. SHALL BE INSTALLED
- SUCH THAT THE TOP OF THE EQUIPMENT IS 72" AFF, UOI. REFER TO THE MECHANICAL/PLUMBING DRAWINGS TO VERIFY EQUIPMENT LOCATIONS AND COORDINATION OF STARTERS, DISCONNECT SWITCHES.

GENERAL LIGHTING NOTES

- 1. SEE NEC ARTICLE 410 FOR MORE INFORMATION REGARDING
- LIGHTING FIXTURES 2. LIGHTING CIRCUITS ABOVE THE BAR JOIST OR IN CONCEALED
- AREAS MAY BE FLEXIBLE WIRING UOI. 3. LIGHT SWITCHES SHALL BE MOUNTED AT 48" TO THE BOTTOM OF THE BOX, UOI.
- 4. LAY IN TYPE LIGHTING FIXTURES SHALL BE SUPPORTED BY EITHER OF TWO METHODS:
- 4.1. THEY SHALL BE SECURELY ATTACHED TO THE CEILING GRID BOLTS, SCREWS, RIVETS, OR LISTED CLIPS IDENTIFIED FOR USE WITH THE CEILING MANUFACTURER
- THEY SHALL BE ATTACHED TO THE BUILDING STRUCTURE BY AN INDEPENDENT MEANS (CEILING WIRE) AND COLOR CODED TO DISTINGUISH THIS SUPPORT FROM THE CEILING GRID SUPPORT SYSTEM.
- 5. A RECESSED LIGHTING FIXTURE THAT IS NON-TYPE IC SHALL HAVE ALL RECESSED PARTS SPACED NOT LESS THAN 1/2" FROM COMBUSTIBLE MATERIALS
- 6. ALL 2' X 2' LIGHT FIXTURES SHALL BE ORIENTED SUCH THAT LONG EDGE OF LAMPS RUN THE SAME DIRECTION THROUGHOUT THE FACILITY.
- ALL EMERGENCY/EGRESS FIXTURES AND SIGNS MOUNTED ABOVE DOORWAYS SHALL SHALL CENTER MTD ON WALL ABOVE DOOR HEADER, UOI
- 8. OUTLET BOXES OR FITTINGS INSTALLED AS REQUIRED BY ARTICLE 314.23 SHALL BE PERMITTED TO SUPPORT LIGHTING
- FIXTURES. DURING INSTALLATION, IF AN OBVIOUS CONFLICT IS DISCOVERED BETWEEN LIGHTING FIXTURES AND OTHER BUILDING ELEMENTS (STRUCTURE, HVAC, PLUMBING, SPRINKLER, ETC.) THE CONTRACTOR HAS THE AUTHORITY TO MAKE MINOR ADJUSTMENTS TO THE FIXTURE LAYOUT. OTHER ADJUSTMENTS SHALL BE APPROVED BY THE ENGINEER OF RECORD.
- 10. LIGHT FIXTURES HAVE BEEN SELECTED TO BE OF PROPER CONSTRUCTION AND LISTED FOR THE ENVIRONMENT. ANY DEVIATION IN THE TYPE OR LOCATION SHALL BE APPROVED BY THE ENGINEER OF RECORD.
- 11. SEE ARCHITECTURAL REFLECTED CEILING PLANS (WHERE AVAILABLE) FOR EXACT LOCATION OF ALL CEILING MOUNTED **EQUIPMENT**
- 12. LIGHT FIXTURES SHALL NOT BE USED AS A RACEWAY, UNLESS

THESE DRAWINGS.

- LISTED AND MARKED FOR THAT PURPOSE. THESE DRAWINGS SHOW THE INTENT OF THE DESIGNER. EVERY WIRE IS NOT ILLUSTRATED (EXAMPLES: WIRING BETWEEN 3-WAY SWITCHES, WIRING FOR AN EMERGENCY BALLAST, ETC.) ON
- 14. THE INSTALLER SHOULD REFER TO THE DETAILS FOR THE PROPER WIRING OF OCCUPANCY SENSORS. COORDINATE WITH
- 15. CONDUITS, LIGHTING FIXTURES, ETC SHALL NOT BE MOUNTED DIRECTLY BELOW SMOKE/HEAT VENTS, SPRINKLER HEADS, EVAPORATOR VENTS OR SKY LIGHTS. 16. THE ARCHITECT/ENGINEER RESERVES THE RIGHT TO REJECT
- ANY AND ALL FIXTURES NOT PRE-APPROVED BY ARCHITECT/ENGINEER 10 DAYS PRIOR TO BID. 17. ALL OCCUPANCY SENSORS SHALL BE SET WITH A 10 MINUTE TIME OUT, WITH THE EXCEPTION OF RESTROOM SENSORS. ALL
- 18. CONTRACTOR SHALL PROVIDE ALL COMPONENTS REQUIRED

RESTROOM SENSORS SHALL BE SET WITH A 20 MINUTE TIME


- FOR PROPER OPERATION OF FIXTURES. 19. CONTRACTOR SHALL REFER TO LATEST ARCHITECTURAL
- DRAWINGS FOR EXACT MOUNTING HEIGHTS. 20. SHORT DASHED CIRCUITS REPRESENT CIRCUITS WHICH ARE EMERGENCY OR UN-SWITCHED NIGHT LIGHT CIRCUITS. EACH FIXTURE WITH AN EMERGENCY BALLAST REQUIRES A WIRE WHICH IS CONSTANTLY HOT (NOT SWITCHED) FOR PROPER OPERATION.IF NIGHT LIGHT CIRCUIT, CIRCUIT FIXTURES AHEAD
- OF ANY SWITCHES OR SENSORS 21. ALL LIGHTING LAYOUTS ARE BASED ON REFLECTED CEILING PLANS. DO NOT ALTER THE NUMBER OF FIXTURES INDICATED ON DRAWINGS. SEE FIXTURE SCHEDULE FOR APPLICABLE
- 22. CONTRACTOR SHALL PROVIDE POWER PACKS FOR OCCUPANCY SENSORS AS REQUIRED BY MANUFACTURER. PROVIDE 120V
- CIRCUITS FROM NEAREST 120V PANEL AS REQUIRED 23. CONTRACTOR SHALL PROVIDE ALL ACCESSORIES FOR OPERATION OF OCCUPANCY SENSORS, INCLUDING FOR USE
- WITH MECHANICAL LOADS EXHAUST FANS. 24. CONTRACTOR SHALL CONCEAL ALL WIRES AND DEVICES WHERE POSSIBLE. IN AREAS WHERE CONCEALMENT IS NOT PRACTICAL, PROVIDE WIREMOLD PAINTED TO MATCH FINISHES. COORDINATE EXACT REQUIREMENTS WITH ARCHITECT

GENERAL GROUNDING NOTES

- ALL GROUND RODS SHALL BE 3/4" X 10' COPPER-CLAD STEEL UOI. EVERY EFFORT SHOULD BE MADE TO INSTALL THE GROUND RODS IN A VERTICAL POSITION. IF THIS IS NOT POSSIBLE, IN SOME CASES, THE ENGINEER MAY REQUIRE THE INSTALLATION OF A PLATE ELECTRODE OR HE MAY APPROVE AN ANGLED OR HORIZONTAL INSTALLATION OF A GROUND ROD.
- GROUND RODS AND THE GROUND RING CONDUCTORS SHALL BE LOCATED 24" MINIMUM FROM THE STRUCTURAL FOUNDATION AND SHALL BE BURIED 30" MINIMUM BELOW FINISHED GRADE (REFERENCE NEC 250.52.F).
- IN GENERAL, THE GROUND LOOP SHALL CONSIST OF 4/0 STRANDED BARE COPPER UOI. WHEREVER BARE GROUNDING SYSTEM CONDUCTORS PASS THROUGH OR TERMINATE IN CONCRETE, THE EXPOSED COPPER CONDUCTOR MUST BE PAINTED WITH A PVC TYPE PAINT TO HELP PROTECT AGAINST CORROSION.
- THE GROUNDING SYSTEM SHALL BE TESTED USING THE FALL OF POTENTIAL METHOD TO ENSURE COMPLIANCE WITH THE SPECIFICATIONS AND THE NEC MINIMUM REQUIREMENTS
- ALL CONNECTIONS OF WIRE-TO-WIRE, WIRE-TO-ROD, AND WIRE-TO-STEEL SHALL BE MADE EXOTHERMICALLY USING APPROPRIATE MOLDS OR APPROVED CLAMPS.
- 6. IF NECESSARY, THE AUTHORITY HAVING JURISDICTION SHALL BE CALLED IN TO INSPECT THE INSTALLATION OF THE GROUNDING SYSTEM BEFORE IT IS BURIED OR COVERED.
- THE GROUNDING SHOWN ON THESE DRAWINGS INCLUDE THE MINIMUM REQUIREMENTS. ALL THE REQUIREMENTS OF THE NEC ARTICLE 250 MUST BE
- 8. METAL RACEWAYS FOR SERVICE CONDUCTORS AND EQUIPMENT SHALL BE GROUNDED. A METAL ELBOW THAT IS INSTALLED IN AN UNDERGROUND INSTALLATION OF RIGID NON-METALLIC CONDUIT AND IS ISOLATED FROM POSSIBLE CONTACT BY A MINIMUM COVER OF 18" TO ANY PART OF THE ELBOW SHALL NOT BE REQUIRED TO BE GROUNDED.
- NON-CURRENT-CARRYING CONDUCTIVE MATERIALS, SUCH AS METAL CONDUIT, JUNCTION BOXES, ETC., ENCLOSING ELECTRICAL CONDUCTORS OR EQUIPMENT OR FORMING PART OF SUCH EQUIPMENT, SHALL BE GROUNDED.
- 10. THE NON-CURRENT-CARRYING METAL PARTS OF SERVICE EQUIPMENT (RACEWAYS AND ENCLOSURES CONTAINING SERVICE CONDUCTORS, INCLUDING METER FITTINGS, BOXES, OR THE LIKE, INTERPOSED IN THE SERVICE RACEWAY OR ARMOR SHALL BE BONDED TOGETHER. BONDING SHALL APPLY AT EACH END AND TO ALL INTERVENING RACEWAYS, BOXES, AND ENCLOSURES BETWEEN THE SERVICE EQUIPMENT AND THE GROUNDING ELECTRODE. METHODS OF BONDING SHALL INCLUDE EXOTHERMIC WELDING, LISTED PRESSURE CONNECTORS LISTED CLAMPS, CONNECTIONS UTILIZING THREADED COUPLINGS OR THREADED BOSSES ON ENCLOSURES WHERE MADE UP WRENCH-TIGHT, OTHER APPROVED DEVICES, SUCH AS BONDING-TYPE LOCKNUTS AND BUSHINGS
- 11. NONCONDUCTIVE COATINGS (SUCH AS PAINT, LACQUER, AND ENAMEL) ON EQUIPMENT TO BE GROUNDED SHALL BE REMOVED FROM THREADS AND OTHER CONTACT SURFACES TO ENSURE GOOD ELECTRICAL CONTINUITY OR BE CONNECTED BY MEANS OF FITTINGS DESIGNED SO AS TO MAKE SUCH REMOVAL
- 12. WHERE THE TRANSFORMER SUPPLYING THE SERVICE IS LOCATED OUTSIDE THE BUILDING, AT LEAST ONE ADDITIONAL GROUNDING CONNECTION SHALL BE MADE FROM THE GROUNDED SERVICE CONDUCTOR TO A GROUNDING ELECTRODE, EITHER AT THE TRANSFORMER OR ELSEWHERE OUTSIDE THE BUILDING.
- 13. FOR A GROUNDED SYSTEM, AN UN-SPLICED MAIN BONDING JUMPER SHALL BE USED TO CONNECT THE EQUIPMENT GROUNDING CONDUCTOR(S) AND THE SERVICE-DISCONNECT ENCLOSURE TO THE GROUNDED CONDUCTOR OF THE SYSTEM MAIN BONDING JUMPERS SHALL BE OF COPPER OR OTHER CORROSION-RESISTANT MATERIAL. A MAIN BONDING JUMPER SHALL BE A WIRE BUS, SCREW, OR SIMILAR SUITABLE CONDUCTOR. THE MAIN BONDING JUMPER SHALL NOT BE SMALLER THAN THE SIZES SHOWN IN TABLE 250.66 OF THE NEC
- FOR GROUNDING ELECTRODE CONDUCTORS. METAL RACEWAYS, CABLE TRAYS, ENCLOSURES, FRAMES, FITTINGS, AND OTHER METAL NON-CURRENT-CARRYING PARTS THAT ARE TO SERVE AS GROUNDING CONDUCTORS, WITH OR WITHOUT THE USE OF SUPPLEMENTARY EQUIPMENT GROUNDING CONDUCTORS, SHALL BE EFFECTIVELY BONDED WHERE NECESSARY TO ENSURE ELECTRICAL CONTINUITY AND THE CAPACITY TO
- CONDUCT SAFELY ANY FAULT CURRENT LIKELY TO BE IMPOSED ON THEM 15. EXPOSED NON-CURRENT-CARRYING METAL PARTS OF FIXED EQUIPMENT LIKELY TO BECOME ENERGIZED SHALL BE GROUNDED UNDER ANY OF THE FOLLOWING
- **CONDITIONS:** 15.1. WHERE WITHIN' 8' VERTICALLY OR 5' HORIZONTALLY OF GROUND OR GROUNDED METAL OBJECTS AND SUBJECT TO CONTACT BY PERSONS
- 15.2. WHERE LOCATED IN A WET OR DAMP LOCATION AND NOT ISOLATED WHERE IN ELECTRICAL CONTACT WITH METAL 15.4. WHERE SUPPLIED BY A METAL-CLAD, METAL-SHEATHED, METAL-RACEWAY,
- OR OTHER WIRING METHOD THAT PROVIDES AN EQUIPMENT GROUND 15.5. WHERE EQUIPMENT OPERATES WITH ANY TERMINAL AT OVER 150 VOLTS TO
- 16. ALL GROUNDING CONDUCTORS AND BONDING JUMPERS SHALL BE ROUTED TO ENSURE SHORTEST POSSIBLE CONDUCTOR LENGTH. 17. BONDING JUMPERS MEETING THE OTHER REQUIREMENTS OF THIS ARTICLE
- SHALL BE USED AROUND CONCENTRIC OR ECCENTRIC KNOCKOUTS THAT ARE PUNCHED OR OTHERWISE FORMED SO AS TO IMPAIR THE ELECTRICAL CONNECTION TO GROUND. STANDARD LOCKNUTS OR BUSHINGS SHALL NOT BE THE SOLE MEANS FOR THE BONDING REQUIRED BY THIS SECTION.



OCIA




_		
	REVISIO	ONS .
	No.	Date


ELECTRICAL


AS SHOWN SHEET NUMBER


DATE OF ORIGINAL ISSUE 6/9/2024














20' 60" 18"

Pole And Foundation Detail
Not to Scale



ARCHIT

uildin


 \Box


 ∞

REVISION	18
No.	Date


PHOTOMETRICS ELECTRICAL

A202
SCALE
AS SHOWN
SHEET NUMBER
E100
OF
DATE OF ORIGINAL ISSUE
6/9/2024










PHOTMETRICS -ELECTRICAL



KEYNOTES:

Retail Building
7418 Hwy 70
Bartlett, TN

I			
	REVISIO	DNS	
	No.	Date	
			·
			-

FLOOR PLAN -ELECTRICAL

> OF DATE OF ORIGINAL ISSUE 6/9/2024

FLOOR PLAN — ELECTRICAL 1/8"=1'-0"